

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	BITUMINOUS SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	H.M.A. SURFACE REMOVAL 0.75 IN	H.M.A. SURFACE REMOVAL 1.5 IN	POLY BIT MATERIALS PRIME COAT	AGGREGATE MATERIALS PRIME COAT	POLYMERIZED LEVELING BINDER(MM) IL 4.75 N50	H.M.A. SURFACE COURSE MIX "D", N50	INCIDENTAL H.M.A. SURFACING	HOT MIX ASPHALT SURFACE COURSE MIX C N30				AGGREGATE SHOULDERS TYPE B				HOT-MIX ASPHALT SHOULDERS 8"			
													LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE	LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE	LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	SQ YD	TON	SQ YD	TON	SQ YD	TON	SQ YD	TON	SQ YD	TON	SQ YD	TON
SIDEROADS																								
Hennepin/Florid Road (East)	40 - 120	56	464.76	464.76	44.44			0.19	0.93			39.04				30.74	5.25	26.50	4.53					
Hennepin/Florid Road (West)	26 - 27.5	61.3	332.97	332.97	30.56			0.13	0.67			27.97				25.67	4.39	30.43	5.20					
Umikis Drive (North A)	16.5 - 19	16	72.17	72.17	18.34			0.03	0.14			6.06				7.00	1.20	12.39	2.12					
Umikis Drive (North B)	17 - 18	22	88.00	88.00	20.00			0.04	0.18			7.39				9.27	1.58	9.91	1.69					
Hennepin Farms Road (North)	33 - 36.5	28.25	226.74	226.74	36.66			0.09	0.45			19.05				10.13	1.73	20.47	3.50					
Umikis Drive (South)	44.8 - 48	19.7	101.56					0.23	0.20			8.53				9.84	1.68	12.76	2.18					
Hennepin Farms Road (South)	23.5 - 25.5	27.5	166.03	166.03	28.34			0.07	0.33			13.95				13.21	2.26	14.00	2.39					
675N	33 - 36	25	163.88	163.88	40.00			0.07	0.33			13.77				11.55	1.97	11.79	2.01					
600N (West)	18 - 22	30.5	157.51	157.51	24.44			0.06	0.32			13.23				13.68	2.34	13.27	2.27					
600N (East)	28	23.4	137.18	137.18	31.12			0.05	0.27			11.52				11.93	2.03	10.80	1.84					
550N	20	27.3	133.99	133.99	22.22			0.05	0.27			11.26				12.28	2.10	12.04	2.06					
McNabb Blacktop (CH 11)	22 - 24.5	41.5	275.93	275.93	27.22			0.11	0.55			23.18				19.68	3.36	18.86	3.22					
350N	20	32	186.67	186.67	22.22			0.07	0.37			15.68				13.96	2.38	16.56	2.83					
Clear Creek Road	23 - 24	21.8	102.87	102.87	26.66			0.04	0.21			8.64				11.31	1.93	7.81	1.33					
Taylor Road (North)	21	42.5	112.00	112.00	23.34			0.04	0.22			9.41				21.93	3.75							
Taylor Road (South)	23 - 31	39	131.00	131.00	25.56			0.05	0.26			11.00						21.55	3.68					
Spotted Dutchman Hill Road	30 - 36	25.5	191.17	191.17	40.00			0.08	0.38			16.06				14.00	2.39	14.61	2.50					
PRIVATE ENTRANCES (36)	Variable	Variable	Variable					0.87	8.64			362.88												
MAILBOX TURNOUTS (10)	Variable	Variable	Variable					0.11	1.11			46.70												
3 INCH WEDGE	0.25	55337.00	1537.14				1537.14	0.61	3.07		129.12													
SUB-TOTAL SHEET 2				2,943	461		1,537	3	19	0	129.12	665.32				236.18	40.34	253.75	43.35					
													TOTAL	0	0	TOTAL	490	84	TOTAL	0	0			

SURFACE TYPE	BIT PR COAT (GAL/SQ YD)	AGG PR COAT (LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW BITUMINOUS COURSES	0.03	2

SURFACE TYPE	CONVERSION FACTOR
BIT. SURF. COURSES	112 LB /SQ YD/IN
ALL OTHER BIT.	112 LB /SQ YD/IN
AGGREGATE SHOULDERS	2.05 TONS/CLYD

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
RESURFACING SCHEDULE SHEET 2 OF 3**

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2370	(1,2)RS-2	PUTNAM	32	15
CONTRACT NO. 68558			ILLINOIS FED. AID PROJECT	

FILE NAME = D468958-CADD.dgn

USER NAME = tuesmandr
DESIGNED -
DRAWN -
CHECKED -
DATE -

REVISIONS
REVISION -
REVISION -
REVISION -
REVISION -

PLOT SCALE = 4999.9998 ' / IN.
PLOT DATE = 1/27/2010

SCALE: SHEET NO. OF SHEETS STA. TO STA.