

GUTTER REMOVAL	
LOCATION	FOOT
Rt Sta 78+35 to 87+11	876
Lt Sta 166+13 to 181+33	1520
TOTAL	2,396

REMOVING INLETS	
LOCATION	EACH
Rt Sta 85+85	1
Rt Sta 81+98	1
Lt Sta 166+16	1
Lt Sta 170+08	1
Lt Sta 174+13	1
TOTAL	5

INSERTION CULVERT LINER 42"	
LOCATION	FOOT
CL Sta. 392+64	61
TOTAL	61

SUB-BASE GRANULAR MATERIAL, TYPE B	
LOCATION	TON
Umikas Drive CL Lt. Sta 179+50	56
TOTAL	56

H.M.A. BINDER COURSE. IL 19.0, N50	
LOCATION	TON
Umikas Drive CL Lt. Sta 179+50	73
STA 475+47 TO STA 478+53	63
TOTAL	136

PAVEMENT REMOVAL	
LOCATION	SQ YD
Umikas Drive CL Lt. Sta 179+50	163
TOTAL	163

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

MATERIAL TRANSFER DEVICE	
LOCATION	TON
MAINLINE SURFACE	10868
TOTAL	10,868

SHOULDER RUMBLE STRIP	
LOCATION	FOOT
EXISTING HMA SHOULDERS	
Lt & Rt Sta 25+85 to 58+02	2336.8
Rt Sta 239+62 to 240+42	80
Lt & Rt Sta 240+42 to 241+78	272
Lt & Rt Sta 243+45 to 244+64	238
Lt Sta 244+64 to 245+54	90
Lt & Rt Sta 294+53 to 295+03	100
Lt & Rt Sta 460+85 to 463+00	430
Lt & Rt Sta 465+00 to 466+50	300
Lt Sta 466+50 to 467+34	84
Rt Sta 474+43 to 478+53	410
Lt Sta 474+71 to 479+00	429
Lt Sta 620+92 to 621+40	48
Lt & Rt Sta 621+40 to 623+48	416
Lt & Rt Sta 624+32 to 625+82	300
NEW HMA SHOULDERS	
Lt Sta 71+30 to 87+11	1581
Rt Sta 71+30 to 87+40	1610
Lt Sta 109+00 to 179+04	7004
Lt Sta 180+08 to 189+03	895
Rt Sta 109+00 to 165+30.5	5630.5
Rt Sta 166+19.5 to 187+05	2085.5
TOTAL	24,340

TRAFFIC CONTROL AND PROTECTION STANDARD 701201	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION STANDARD 701306	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION STANDARD 701326	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

ENGINEER'S FIELD OFFICE TYPE A	
LOCATION	CAL MO
JOBSITE	4
TOTAL	4

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	1
TOTAL	1

EXCAVATING AND GRADING EXISTING SHOULDER	
LOCATION	UNIT
EXISTING HMA SHOULDERS	
Lt & Rt Sta 25+85 to 58+02	23.4
Rt Sta 239+62 to 240+42	0.8
Lt & Rt Sta 240+42 to 241+78	2.7
Lt & Rt Sta 243+45 to 244+64	2.4
Lt Sta 244+64 to 245+54	0.9
Lt & Rt Sta 294+53 to 295+03	1
Lt & Rt Sta 460+85 to 463+00	4.3
Lt & Rt Sta 465+00 to 466+50	3
Lt Sta 466+50 to 467+34	0.85
Rt Sta 474+43 to 478+53	4.1
Lt Sta 474+71 to 479+00	4.3
Lt Sta 620+92 to 621+40	0.5
Lt & Rt Sta 621+40 to 623+48	4.2
Lt & Rt Sta 624+32 to 625+82	3
NEW HMA SHOULDERS	
Lt Sta 71+30 to 87+11	15.8
Rt Sta 71+30 to 87+40	16.1
Lt Sta 109+00 to 179+04	70
Lt Sta 180+08 to 189+03	9
Rt Sta 109+00 to 165+30.5	56.3
Rt Sta 166+19.5 to 187+05	20.9
TOTAL	244

PROTECTIVE COAT	
LOCATION	SQ YD
S.N. 078-0034 - DECK & PARAPET	168
S.N. 078-0036 - DECK & PARAPET	602
S.N. 078-0037 - DECK & PARAPET	492
TOTAL	1,262

MOWING	
LOCATION	UNIT
JOBSITE	1107
TOTAL	1,107

CONSTRUCTION STATION LAYOUT	
LOCATION	L SUM
JOBSITE	1
TOTAL	1