

CCC&G AND MEDIAN SCHEDULE									
LOCATION	CCC&G REMOVAL	CONCRETE MEDIAN SURFACE REMOVAL	CONCRETE MEDIAN REMOVAL	CCC&G, TYPE B-6.06	CONCRETE MEDIAN SURFACE, 6"	CONCRETE MEDIAN, TYPE SB-6.06	CONCRETE MEDIAN, TYPE SB-6	PAVEMENT FABRIC	PRISMATIC CURB REFLECTOR
	FT	SQ FT	SQ FT	FT	SQ FT	SQ FT	SQ FT	SQ YD	EACH
STA. 79+50.00 TO STA. 83+24.90	767.29	6,495.08		654.88	5,893.92	601.16		66.80	39
STA. 83+89.25 TO STA. 97+46.00			19,903.32				19,903.32	2211.48	88
STA. 98+10.13 TO STA. 103+08.00			4,642.34				4,642.34	515.82	56
TOTAL	767	6,495	24,546	655	5,894	601	24,546	2,794	183

SCHEDULE OF GUARDRAIL QUANTITIES				
LOCATION	TRAFFIC BARRIER TERMINAL REMOVAL, TY 1	TRAFFIC BARRIER TERMINAL TY 1, SPECIAL (TANGENT)	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL AGG. EROSION CONTROL
	EACH	EACH	EACH	TON
LT. STA. 436+40.00	1	1	1	5.07
RT. STA. 436+40.00	1	1	1	5.07
LT. STA. 438+00.00	1	1	1	5.07
RT. STA. 438+00.00	1	1	1	5.07
LT. STA. 483+92.00	1	1	1	5.07
LT. STA. 485+65.00	1	1	1	5.07
RT. STA. 2461+00.00	1	1	1	5.07
RT. STA. 2464+65.00	1	1	1	5.07
RT. STA. 2494+59.00	1	1	1	5.07
LT. STA. 2495+40.00	1	1	1	5.07
RT. STA. 2500+06.00	1	1	1	5.07
LT. STA. 2500+86.00	1	1	1	5.07
TOTAL:	12	12	12	61

NOTE: STATIONS ARE APPROXIMATE

CLASS D PATCH - 14 IN					
PATCHING UNIT	LOCATION		TYPE II	TYPE III	TYPE IV
			SQ YD	SQ YD	SQ YD
1	STA. 395+69.00	TO STA. 436+40.00	451.11	37.33	186.67
2	STA. 436+40.00	TO STA. 531+44.00	214.67	49.78	
3	STA. 531+44.00	TO STA. 571+04.00	121.33		
4	STA. 571+04.00	TO STA. 625+42.00	74.67		
5	STA. 625+42.00	TO STA. 678+22.00	46.67		
6	STA. 678+22.00	TO STA. 731+02.00	140.00		
7	STA. 731+02.00	TO STA. 738+15.60 BK	102.67		
	STA. 2386+15.80 AH	TO STA. 2427+60.00			
8	STA. 2427+60.00	TO STA. 2506+81.00	140.00	15.56	
9	STA. 2506+81.00	TO STA. 2546+24.00	62.22		
10	STA. 2546+24.00	TO STA. 2599+00.00	74.67		
11	STA. 2599+00.00	TO STA. 2638+70.00	140.00		
12	STA. 2638+70.00	TO STA. 2691+60.00	140.00		
13	STA. 2691+60.00	TO STA. 2704+30.00 BK	46.67		
	STA. 70+00.00 AH	TO STA. 117+77.91 BK			31.11
14	STA. 745+26.71 AH	TO STA. 798+20.00	823.33	33.78	137.78
15	STA. 798+20.00	TO STA. 851+20.00	308.00		
SUB-TOTAL			2,886.01	136.45	355.56
TOTAL			2,886	136	356

FILE NAME = 68570 - Phase II.dgn

USER NAME = johnsonv
 PLOT SCALE = 100.0000 / IN.
 PLOT DATE = 2/1/2010

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 7 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	31RS-2+30,39RS-3+32,33RS-4	WOODFORD	41	20
CONTRACT NO. 68570				
ILLINOIS FED. AID PROJECT				