SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80/20 FED/ST CONSTRUCTION CODE Henry Co. ROADWAY I000 RURAL	Knox Co. ROADWAY I000 RURAL
20200100	EARTH EXCAVATION	CU YD	98	98	
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	389	389	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	90	13	77
40600300	AGGREGATE (PRIME COAT)	TON	519	73	446
40600825	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N50	TON	6973	1027	5946
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	215	37	178
40600990	TEMPORARY RAMP	SQ YD	80	13	67
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	14616	2064	12552
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	209	49	160
42001300	PROTECTIVE COAT	SQ YD	578		578
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	139501	24392	115109
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	6997		6997
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	26077		26077
44001600	BRIDGE WEARING SURFACE REMOVAL	SQ YD	273		273
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1457	64	1393
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	160		160
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	174		174
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2540	380	2160
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	0.45	2.55
67100100	MOBILIZATION	L SUM	1		1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	0.15	0.85
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	0.15	0.85