

EPOXY PAVEMENT MARKING LINE - 4 and TEMPORARY PAVEMENT MARKING LINE

4" Yellow - No Passing Zone NBL

| | | | |
|-----------|----|--------|-------|
| Henry Co. | | | foot |
| 107+00 | to | 111+89 | 489 |
| 107+71 | to | 112+40 | 469 |
| sub-total | | | 958 |
| Knox Co. | | | |
| 112+40 | to | 134+74 | 2234 |
| 58+38 | to | 73+40 | 1502 |
| 85+64 | to | 95+00 | 936 |
| 112+35 | to | 145+76 | 3341 |
| 136+26 | to | 145+76 | 950 |
| 159+49 | to | 169+55 | 955 |
| 191+50 | to | 232+18 | 4068 |
| 240+79 | to | 249+08 | 829 |
| 286+66 | to | 292+90 | 624 |
| 306+63 | to | 363+13 | 5650 |
| sub-total | | | 21089 |

4" Yellow - No Passing Zone SBL

| | | | |
|-----------|----|--------|-------|
| Henry Co. | | | foot |
| 107+71 | to | 112+40 | 469 |
| Knox Co. | | | |
| 112+40 | to | 124+94 | 1254 |
| 56+08 | to | 66+28 | 1020 |
| 81+51 | to | 91+07 | 956 |
| 109+00 | to | 136+26 | 2726 |
| 151+04 | to | 159+49 | 845 |
| 187+83 | to | 222+15 | 3432 |
| 232+18 | to | 246+44 | 1426 |
| 279+70 | to | 284+98 | 528 |
| 296+08 | to | 307+00 | 1093 |
| 318+25 | to | 353+10 | 3485 |
| 413+29 | to | 418+00 | 471 |
| sub-total | | | 17235 |

4" Yellow Skip Dash

| | | | |
|-----------|----|--------|---------|
| Henry Co. | | | foot |
| 107+00 | to | 124+54 | 438.5 |
| 30+00 | to | 107+71 | 1943 |
| sub-total | | | 2381.25 |
| Knox Co. | | | |
| 124+94 | to | 265+11 | 3504 |
| 0+00 | to | 59+16 | 1460 |
| 66+28 | to | 85+64 | 484 |
| 91+07 | to | 112+35 | 532 |
| 136+26 | to | 191+50 | 1381 |
| 222+15 | to | 240+79 | 466 |
| Knox Co. | | | |
| 246+44 | to | 306+63 | 1505 |
| 307+00 | to | 318+25 | 281 |
| 353+10 | to | 418+00 | 1623 |
| sub-total | | | 11255 |

White Edge Line 4"

| | | | |
|-----------|----|--------|----------|
| Henry Co. | | | foot |
| 107+00 | to | 124+54 | 3508 |
| 30+00 | to | 112+40 | 16480 |
| sub-total | | | 19988 |
| Knox Co. | | | |
| 112+40 | to | 265+11 | 30542.6 |
| 0+00 | to | 172+27 | 34453.52 |
| 172+04 | to | 418+00 | 49192.1 |
| sub-total | | | 114188.2 |

Temporary Pav't Marking Line & Epoxy Pav't Marking Line Letters & Symbols

| | | | |
|----------------|-----|-------|----|
| 58+70 | RXR | 57.6 | sf |
| 71+27 | RXR | 57.6 | sf |
| Knox Co. total | | 115.2 | sf |

Short Term Pav't Mkg

| | | | |
|----------------|----|--------|-------|
| Henry Co. | | | foot |
| 107+00 | to | 124+54 | 193 |
| 30+00 | to | 112+40 | 906 |
| sub-total | | | 1099 |
| 4 applications | | | 4397 |
| Knox Co. | | | |
| 112+40 | to | 265+11 | 1680 |
| 0+00 | to | 172+27 | 1895 |
| 172+04 | to | 418+00 | 2706 |
| sub-total | | | 6280 |
| 4 applications | | | 25122 |

Work Zone Pav't Mkg Rem

| | | |
|-----------|--------|-------|
| Henry Co. | | Sq Ft |
| 1099 | x 0.33 | 363 |
| Knox Co. | | |
| 6280 | x 0.33 | 2073 |

Mowing

| | | | |
|-----------|----|--------|------|
| Henry Co. | | | Unit |
| 107+00 | to | 124+54 | 18 |
| 30+00 | to | 107+71 | 78 |
| sub-total | | | 95 |
| Knox Co. | | | |
| 112+40 | to | 265+11 | 153 |
| 0+00 | to | 172+27 | 172 |
| 172+04 | to | 418+00 | 246 |
| sub-total | | | 571 |

Temporary Pav't Marking Ln 24" & Epoxy Pav't Marking Ln 24"

| | | | |
|-------------------------|--------|----|----|
| 58+70 | at RXR | 24 | lf |
| 71+27 | at RXR | 24 | lf |
| "STOP" bars at crossing | | 24 | lf |
| Knox Co. total | | 72 | lf |

Raised Reflective Pav't Mkrs

| | | | |
|-----------|----|--------|------|
| Henry Co. | | | each |
| 107+00 | to | 124+54 | 22 |
| 30+00 | to | 112+40 | 103 |
| sub-total | | | 125 |
| Knox Co. | | | |
| 112+40 | to | 265+11 | 191 |
| 0+00 | to | 172+27 | 215 |
| 172+04 | to | 418+00 | 307 |
| sub-total | | | 713 |

Raised Reflective Pav't Mkr Removal

| | | | |
|-----------|----|--------|------|
| Knox Co. | | | each |
| 112+40 | to | 265+11 | 191 |
| 0+00 | to | 172+27 | 215 |
| 172+04 | to | 418+00 | 307 |
| sub-total | | | 713 |

Protective Coat
Pope Creek SN 048-0026 578 sy

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|--------------------|-----------------------------|------------|---------------------------|-----------|
| F.A.S. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 1190 | 123RS-4,124RS-5,125,126RS-3 | Knox/Henry | 20 | 10 |
| CONTRACT NO. 68604 | | | ILLINOIS FED. AID PROJECT | |

FILE NAME = D468604-sht-plan.dgn

USER NAME = leyndm
DESIGNED -
DRAWN -
PLOT SCALE = 488,0000' / IN.
CHECKED -
PLOT DATE = 1/27/2010
DATE -

REVISOR -
REVISOR -
REVISOR -
REVISOR -