

Aggregate Shoulders Ty B	
LOCATION	TON
LT & RT STA 47+64 - 427+83	4400
TOTAL	4,400

Agg. Surface Course Ty B	
LOCATION	TON
LT & RT STA 57+47 - 427+83	23
TOTAL	23

*Material should be a CA-6 white rock

**To be used behind Incidental Bituminous approaches at gravel driveways

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL. DAY
CLASS B PATCHING	5
INTERSECTION IMPROVEMENT	20
TOTAL	25

MOWING	
LOCATION	UNIT
LT & RT STA 28+00 TO 427+00	399
TOTAL	399

CLASS D PATCH - 15"						
LOCATION	TYPE II		TYPE III		TYPE IV	
	NO. OF PATCHES	SQ YD	NO. OF PATCHES	SQ YD	NO. OF PATCHES	SQ YD
STA 57+47 TO C.R. 1070	21	171	4	64		
C.R. 1070 TO C.R. 1200	53	461	6	96	2	53
C.R. 1200 TO C.R. 1300	49	403	8	149	2	53
C.R. 1300 TO IL 117	29	237				
IL 117 TO C.R. 1600	14	128				
C.R. 1600 TO STA 427+83	10	80				
WINTER BREAK UP 10%		148		30.9		10.6
GRAND-TOTAL	176	1628	14	340	4	117

CLASS B PATCH - 9"				
LOCATION	TYPE II		TYPE III	
	NO. OF PATCHES	SQ YD	NO. OF PATCHES	SQ YD
STA 736+00 to 57+47				
E.B. LANES	15	120		
W.B. LANES	4	43	2	32
WINTER BREAK UP 10%		16.3		3.2
GRAND-TOTAL	19	179	2	35

*Leave concrete 3" below existing pavement surface. Cap patch with Surface Course, Mix "E", N70. This work is to be included in the cost of the patch.

PAVEMENT FABRIC	
LOCATION	SQ YD
CLASS B TYPE III	35
TOTAL	35

DOWEL BARS 1 1/2"	
LOCATION	EACH
CLASS B PATCHES	480
TOTAL	480

SAW CUTS	
LOCATION	FOOT
CLASS B PATCHES	1313
TOTAL	1,313

FILE NAME = D468625-shr-schedule.dgn	USER NAME = dsetzsm	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	104N,RS-5106RS-2107RS-6	WOODFORD	65	13
			CONTRACT NO. 68625	
ILLINOIS FED. AID PROJECT				