

Temporary Ramp	
LOCATION	SQ YD
STA 736+00	26.67
STA 427+83	13.33
SIDE ROADS	573.33
TOTAL	613

CONSTRUCTION TEST STRIP	
LOCATION	EACH
SMART (METAMORA)	1
3P (RURAL 116)	1
TOTAL	2

MATERIAL TRANSFER DEVICE	
LOCATION	TON
POLY HMA SURF "E"	6325
HMA SURF "D" N50	10770
TOTAL	17095

CONSTRUCTION STATION LAYOUT	
LOCATION	L SUM
RESURFACING	1
TOTAL	1

CONSTRUCTION LAYOUT	
LOCATION	L SUM
INTERSECTION IMPROVEMENT	1
TOTAL	1

RESURFACING TABLE														
LOCATION	LENGTH FT	WIDTH FT	AREA SQ YD	POLY BIT. MTL PRIMECOAT TON	AGGREGATE PRIMECOAT TON	HMA SURF. REM. 3/4" SQ YD	HMA SURF. REM. 1.5" SQ YD	HMA SURF. REM. 2" TON	POLY HMA "E", N70, 1.5" TON	POLY HMA L.B. IL 4.75, 3/4" TON	HMA SURF "D", N50, 1.5" TON	HMA SHOULDER TON	INCIDENTAL HMA SURF TON	HMA SURF REM BUTT JOINTS SQ YD
STA 736+00 TO 47+64	10459	57	66240.33	26.50	132.48		66240		5564.19					190.00
STA 47+64 TO 57+47	983	VAR	4751.00	1.90	9.50		4751		399.08					
STA 47+64 TO 57+47 (10' SHLDRS)	983	20	2184.44	0.87	4.37		2184					183.49		
STA 57+47 TO 246+32	18885	30	62950	32.73	188.85	62950				2643.90	5287.80			
STA 246+32 TO 284+60	1828	VAR	9167.00	4.77	27.50	9167				385.01	770.03			
STA 284+60 TO 401+56	13696	30	45653.33	23.74	136.96	45653				1917.44	3834.88			
STA 401+56 TO 423+59	2203	30	7343.33	3.82	22.03		7343			308.42	616.84			
STA 423+59 TO 427+83	424	35	1648.88	0.86	4.95		1649			53.42	106.85	39.57		118.67
SIDE ROADS														
SUSAN LN	30	VAR	139.60	0.06	0.28								11.73	139.60
WASHINGTON RD	341	VAR	1981.20	0.78	3.92		1981		164.74	12.60				80.00
DOUGLAS ST	366	VAR	1615.60	0.65	3.23		1616		135.71					100.00
ENGLEWOOD	30	VAR	182.90	0.07	0.37								15.38	182.90
N. WASHINGTON ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. WASHINGTON ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. HANCOCK ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. HANCOCK ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. TAZEWELL ST	30	VAR	139.60	0.06	0.28								11.73	139.60
S. TAZEWELL ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. LAFAYETTE ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. LAFAYETTE ST	30	VAR	142.90	0.06	0.29								12.00	142.90
N. HANOVER ST	30	VAR	142.90	0.06	0.29								12.00	142.90
S. HANOVER ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. MENARD ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. MENARD ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. DAVENPORT ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. DAVENPORT ST	30	VAR	157.90	0.06	0.32								13.26	157.90
IL RTE 89	158	VAR	725.00	0.29	1.45		725		60.90					85.00
NILES	30	VAR	156.30	0.06	0.31								13.13	156.30
N. WETMORE ST	30	VAR	146.30	0.06	0.29								12.29	146.30
S. WETMORE ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. SPRING ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. SPRING ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. MORGAN ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. MORGAN ST	30	VAR	136.30	0.05	0.27								11.45	136.30
N. PRAIRIE ST	30	VAR	136.30	0.05	0.27								11.45	136.30
S. PRAIRIE ST	30	VAR	136.30	0.05	0.27								11.45	136.30
HONEYSUCKLE ST	30	VAR	241.40	0.10	0.48								20.28	241.40
PARTRIDGE ST	30	VAR	263.70	0.11	0.53								22.15	263.70
C.R. 1050	30	VAR	110.00	0.04	0.22							3.36	9.24	22.20
C.R. 1070	40	VAR	174.00	0.07	0.35							3.36	14.62	24.40
N. C.R. 1200	30	VAR	110.00	0.04	0.22							2.35	9.24	22.20
S. C.R. 1200	30	VAR	110.00	0.04	0.22							2.35	9.24	22.20
N. C.R. 1300	40	VAR	165.00	0.07	0.33							2.35	13.86	22.20
S. C.R. 1300	40	VAR	165.00	0.07	0.33							2.35	13.86	22.20
C.H. 1	135	VAR	738.00	0.38	2.21			738		31.00	61.99	7.81		66.67
IL RTE 117	157	VAR	1088.00	0.57	3.26			1088		45.70	91.39	8.99		86.67
N. C.R. 1600	45	VAR	197.00	0.08	0.39							3.36	16.55	22.20
S. C.R. 1600	45	VAR	197.00	0.08	0.39							3.36	16.55	22.20
N. 7TH ST	35	VAR	136.20	0.05	0.27							3.36	11.44	136.20
S. 7TH ST	50	VAR	230.30	0.09	0.46							3.36	19.35	230.30
6TH ST	35	VAR	163.40	0.07	0.33								13.73	163.40
ALLEYS (16 LOCATIONS)	10	VAR	432.00	0.17	0.86								36.29	432.00
RURAL ENTRANCES	VAR	VAR	2573.17	0.98	4.91								256	
MAILBOX TURNOUTS	VAR	VAR	460.00	0.18	0.92								38.64	
TOTALS				102	559	117770	86470	1826	6,325	5,397	10,770	269	817	5897

FILE NAME = D468625-sh-t-schedule.dgn	USER NAME = dietzom	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1/80,0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/28/2018	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	1104N,RS-5106RS-2107RS-6	WOODFORD	14	14
CONTRACT NO. 68625			ILLINOIS FED. AID PROJECT	