

EARTHWORK				
LOCATION	EARTH EXCAVATION (CUT)	FOR INFORMATION ONLY		FURNISHED EXCAVATION
		ADJUSTED EARTH EXCAVATION (ADJ. CUT)	EMBANKMENT (FILL)	
	CY	CY	CY	CY
IL 116 STA. 763+50 RT TO IL 116 STA. 765+15 RT	10.0	8.0	114.0	106.0
DOUGLAS ST. STA. 4+00 LT TO DOUGLAS ST. STA. 7+50 LT	145.0	109.0	69.0	-40.0
TOTAL	155	117	183	66

INLET AND PIPE PROTECTION	
LOCATION	EACH
DOUGLAS ST. STA. 6+72.5, 28.71' LT	1
IL 116 STA. 763+92.4, 62.84' RT	1
TOTAL	2

MANHOLES TO BE RECONSTRUCTED WITH NEW T 1 FRAME, CLOSED LID	
LOCATION	EACH
IL 116 STA. 763+92	1
TOTAL	1

HANDHOLE	
LOCATION	EACH
IL 116 STA. 763+94 RT	1
TOTALS	1

TOPSOIL FURNISH AND PLACE, 4"	
LOCATION	SY
DOUGLAS STA. 7+50 LT TO IL 116 STA. 765+15 RT	920
TOTAL	920

PERIMETER EROSION BARRIER	
LOCATION	FOOT
DOUGLAS ST. STA. 6+59.87 LT TO IL 116 STA. 765+13.66 RT	374
TOTAL	374

ENGINEER'S FIELD OFFICE, TY A	
LOCATION	CAL MO
INTERSECTION IMPROVEMENT	5
TOTAL	5

DETECTABLE WARNINGS	
LOCATION	SQ FT
RT STA 764+15	10
TOTAL	10

TC&P STD 701306	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TC&P STD 701602	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TC&P STD 701336	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

TC&P STD 701701	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

*(104)N,RS-5;106RS-2;107RS-6

FILE NAME =
D468625-CADD.dgn

USER NAME = dietzsm
PLOT SCALE = 40,0000' / IN.
PLOT DATE = 1/28/2010

DESIGNED - KJH
DRAWN - JGJ
CHECKED - KJH
DATE -

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P RTE. 673	SECTION •	COUNTY WOODFORD	TOTAL SHEETS 63	SHEET NO. 17
			CONTRACT NO. 68625	

ILLINOIS FED. AID PROJECT