

EAST PEORIA

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE											
				URBAN			TAZEWELL ROADWAY	WOODFORD ROADWAY	TAZEWELL BRIDGE	TAZEWELL SIGNALS	TAZEWELL SIGNALS	TAZEWELL SIGNALS	TAZEWELL FIBER OPT	WOODFORD SIGNALS	WOODFORD FIBER OPT
				1000	1000	SFTY-2A	Y031-1F	Y031-1F	Y031-1F	ITS-Y035	Y031-1F	ITS-Y035			
				80 FED 20 STATE	80 FED 20 STATE	80 FED 20 STATE	80 FED 20 STATE	80/10/10 FED/ST/CIT	80/13.3/6.7 FED/ST/CIT	80 FED 20 STATE	80 FED 20 STATE	80 FED 20 STATE			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	23448	14024	9424										
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	21730	17853	3877										
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	4874	3953	921										
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1527	965	562										
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	4940	4940											
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	11971	4094	7877										
70400100	TEMPORARY CONCRETE BARRIER	FOOT	321	321											
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	321	321											
* 78003100	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LETTERS AND SYMBOLS	SQ FT	298	298											
* 78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	23448	14024	9424										
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1498	1026	472										
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	46	46											
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	15	15											
78300100	PAVEMENT MARKING REMOVAL	SQ FT	124	124											
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1498	1026	472										
* 81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	21523							9718		11805			
* 81021350	CONDUIT PUSHED, 3" DIA., PVC	FOOT	950							540		410			
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	211							211					
* 81300948	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 24" X 24" X 10"	EACH	4							4					
* 81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	13							6		7			
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	21523							9718		11805			
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1									1			

\* SPECIALTY ITEM

FILE NAME = 11116.dgn	USER NAME = hudeisonne	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000" / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/29/2010	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 673	SECTION **	COUNTY TAZE/WOOD	TOTAL SHEETS 60	SHEET NO. 6
CONTRACT NO. 68920			ILLINOIS FED. AID PROJECT	

\*\* 101RS-3; 102RS-4; 103RS-4; 104RS-7