

RESURFACING TABLE (7 OF 7) - TOTALS															
LOCATION	HOT-MIX ASPHALT REMOVAL BUTT JOINT		TEMPORARY RAMP	HOT-MIX ASPHALT REMOVAL 3/4"		HOT-MIX ASPHALT REMOVAL 1 1/2"		POLYMERIZED BITUMINOUS MATERIAL PRIME COAT	AGGREGATE PRIME COAT	POLYMERIZED LEVELING BINDER (MACH METH) IL-4.75 N50 3/4"	POLYMERIZED HOT-MIX ASPHALT SURFACE CSE MIX "E", N70 1 1/2"	INCIDENTAL HOT-MIX ASPHALT SURFACING 1 1/2"	HOT-MIX ASPHALT SHOULDERS		AGGREGATE SHOULDER TYPE B
	RDWY	SHLDR		RDWY	SHLDR	RDWY	SHLDR						1 1/2"	2 1/4"	
	SQ YD	SQ YD		SQ YD	SQ YD	SQ YD	SQ YD						TON	TON	
TAZEWELL COUNTY															
PAGE ONE SUBTOTALS	286.7	111		100589	128.8	12295.1	4246.9							3699.8	0
PAGE ONE TOTALS	377.7		151.2	100717.4		16542		69	415.4	4248.8	9504.4	0	3699.8		1150.3
PAGE TWO SUBTOTALS	106.7	87.7		40568.8	2942.1	11045.6	4319							1381.3	428.5
PAGE TWO TOTALS	194.4		90	43510.9		15364.6		32.4	176.5	1735.1	4343.9	0	1809.8		606.3
PAGE THREE SUBTOTALS	0	0		11689.5	14719.1	595.5	0							0	1899.6
PAGE THREE TOTALS	0		0	26408.6		595.5		12.6	54.1	490.9	982	0	1899.6		964.3
PAGE FOUR SUBTOTALS	2735.2	199.8		12833.4	720	2612.2	5747.1							699.7	0
PAGE FOUR TOTALS	2935		978.4	13553.4		8359.3		13.9	64.8	600	714.1	870.3	699.7		65.2
TAZEWELL COUNTY SUBTOTALS	3109	399		165680	18510	26548	14313							5781	2328
TAZEWELL COUNTY TOTALS	3508		1220	184190		40861		128	711	7075	15544	870	8109		2786
WOODFORD COUNTY															
PAGE FIVE SUBTOTALS	53.4	22.2		0	0	111421	58473.9							5059.2	0
PAGE FIVE TOTALS	75.6		75.6	0		169894.8		70.6	342.6	0	9364	0	5059.2		1073.1
PAGE SIX SUBTOTALS	829.6	22.2		0	0	12005.4	12345.9							1037.3	0
PAGE SIX TOTALS	851.8		851.8	0		24351.3		11.7	50.1	0	527.8	550.2	1037.3		0
WOODFORD COUNTY SUBTOTALS	883	44		0	0	123426	70820							6097	0
WOODFORD COUNTY TOTALS	927		927	0		194246		82	393	0	9892	550	6097		1073
GRAND TOTALS															
COMBINED SUBTOTALS	3992	443		165680	18510	149974	85133							11878	2328
COMBINED TOTALS TOTALS	4435		2147	184190		235107		210	1104	7075	25436	1420	14206		3859

PRIME COAT APPLICATION RATES		
SURFACE TYPE	BITUMINOUS PRIME COAT	AGGREGATE PRIME COAT
	(GAL/SQ YD)	(LB/SQ YD)
ON COLD MILLED SURFACE	0.1	4
EXISTING PAVEMENT	0.05	4
FOG COAT ON NEW BINDER	0.03	2
0.004 TONS PER GALLON FOR BITUMINOUS PRIME COAT		

HMA AND COARSE AGGREGATE APPLICATION RATES	
HMA SURFACE AND BINDER	112 LB/SQ YD IN
ALL OTHER HMA	112 LB/SQ YD IN
COARSE AGGREGATE	2.05 TONS/CU YD

MATERIAL TRANSFER DEVICE	
LOCATION	TONS
WOODFORD COUNTY MAINLINE SURFACE	8719
TAZEWELL COUNTY MAINLINE SURFACE	13287
TOTAL	22006

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

FLEXIBLE DELINEATORS	
LOCATION	EACH
IL 116 MEDIAN AT SPRING CREEK	38
TOTAL	38

CONSTRUCTING TEST STRIP	
LOCATION	EACH
JOBSITE	2
TOTAL	2

ENGINEERING FIELD OFFICE, TYPE A	
LOCATION	CAL MO
JOBSITE	5
TOTAL	5

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
SPRING CREEK	1498
TOTAL	1498

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
JOBSITE	40
TOTAL	40

CHANGEABLE MESSAGE SIGNS	
LOCATION	CAL MO
JOBSITE - 4 SIGNS	20
TOTAL	20

FILE NAME = 11116.dgn	USER NAME = hudeisonme	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/29/2010	DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 673	SECTION **	COUNTY TAZE/WOOD	TOTAL SHEETS 60	SHEET NO. 19
CONTRACT NO. 68920				
ILLINOIS FED. AID PROJECT				

\*\* 101RS-3; 102RS-4; 103RS-4; 104RS-7