

PAVEMENT MARKING TABLE (2 OF 3)

LOCATION	PERMANENT AND TEMPORARY PAVEMENT MARKINGS										PAVEMENT MARKING REMOVAL	PAVEMENT MARKING TAPE TYPE III 4"	SHORT TERM PAVEMENT MARKING (2 APPS)	WORK ZONE PAVEMENT MARKING REMOVAL			
	URETHANE					PREFORMED PLASTIC		RAISED REFLECTIVE PAVEMENT MARKERS									
	4" WHITE	4" YELLOW SINGLE	4" YELLOW DOUBLE	8" WHITE SOLID	8" WHITE SKIP	12" WHITE DIAG	12" YELLOW DIAG	24" WHITE STOP BAR	LETTERS AND SYMBOLS	6" WHITE CENTERLINE					LETTERS AND SYMBOLS	1-WAY CRYSTAL	1-WAY AMBER
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	SQ FT	EACH	EACH	SQ FT	FOOT	FOOT	SQ FT	
TAZEWELL COUNTY																	
SN 090-0110 Stage One														124	2470		823.3
SN 090-0110 Stage Two															2470		823.3
SIDE ROADS																	
Access Road 4	254		254	240		70		40	41.6								
Highview Road	144		144	196		62		34	41.6								
Access Road 5	128		128	140		50		32	41.6								
Mariner Way	188		188	144		50		40	41.6								
Access Road 6	156		156	136		48		36	41.6								
Centennial Drive																	
Marina	44		44	270		89		52	72.8								
Access Road 8	128		128	183		75		40	41.6								
Upper Free Bridge Road	160		160	144		50		40	41.6								
Grosenbach Road	174		174	132		33		33	41.6								
IL 26																	
Spring Creek Road (LT)	106		106					15									
Spring Creek Road (RT)	86		86					15									
Access Road 10	92		92	133		25		18	46.8								
Ronald Road	30																
Fauber Lane	106		106														
Ten Mile Creek Road	144		144														
Upper Spring Bay Road	52		52														
YIELD BARS																	
3 in median at Spring Creek Road														178.8			
2 in median at Ten Mile Creek Road														119.2			
MEDIAN DELINIATION																	
In median 76+57 to 83+36, 94+56 to 96+00			1646					1554					21				
In median at Spring Creek Road			764					375					10				
PAGE TWO SUBTOTALS	1992	0	4372	1718	0	552	1929					0	31				
PAGE TWO TOTALS		6364		1718		2481	395	452.4	0	298		31		124	4940	0	1646.6
TAZEWELL COUNTY SUBTOTALS	58088	56096	6702	17089	763.8	1352	2601					962	64				
TAZEWELL COUNTY TOTALS		120886		17852.8		3953	965	1778.4	14024	298		1026		124	4940	18690	7877

LOCATION	PROTECTIVE COAT	BRIDGE WEARING SURFACE REMOVAL	BRIDGE DECK GROOVING	WIDTH RESTRICTION SIGNING	CONCRETE BRIDGE DECK SCARIFICATION 1/2"	BRIDGE DECK LATEX CONCRETE OVERLAY 2 1/4"	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3
	SQ YD	SQ YD	SQ YD	L SUM	SQ YD	SQ YD	FOOT	FOOT	EACH	EACH
SN 090-0110 (WB)	659	659	659	1	659	659	321	321	1	1
TOTALS	659	659	659	1	659	659	321	321	1	1

FRAMES AND GRATES TO BE ADJUSTED	
LOCATION	EACH
80+61 MEDIAN	1
83+83 MEDIAN	1
96+50 MEDIAN	1
124+82 MEDIAN	1
144+20 MEDIAN	1
187+00 MEDIAN	2
189+00 MEDIAN	1
190+75 MEDIAN	2
191+75 MEDIAN	2
192+40 MEDIAN	1
295+75 MEDIAN	1
HIGHVIEW RD.	2
TOTAL	16

FILE NAME = 11116.dgn	USER NAME = hudsonme	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 1/80.0000 / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/29/2010	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 673	SECTION **	COUNTY TAZE/WOOD	TOTAL SHEETS 66	SHEET NO. 21
			CONTRACT NO. 68920	
ILLINOIS FED. AID PROJECT				

\*\* 101RS-3; 102RS-4; 103RS-4; 104RS-7