

Class B Patching Schedule							
Location	Class B Type II Patch 14"	Class B Type III Patch 14"	Class B Type IV Patch 14"	Dowel Bars	Saw Cuts	Tie Bars 3/4"	Pavement Fabric
	Sq Yd	Sq Yd	Sq Yd	Each	Each	Each	Sq Yd
Start of Project to Highview Road							
Eastbound	96.00	74.67	80.00	320.00	948.00	30.00	154.67
Westbound	26.67	42.67	0.00	100.00	276.00	0.00	42.67
Highview Road to Mariner Way							
Eastbound	349.33	0.00	0.00	740.00	1674.00	0.00	0.00
Westbound	152.00	53.33	81.78	460.00	1214.00	20.00	135.11
Mariner Way to Centennial Drive							
Eastbound	338.67	48.00	653.33	900.00	3420.00	245.00	701.33
Westbound	40.00	74.67	53.33	220.00	642.00	20.00	128.00
Centennial Drive to Marina Lane							
Eastbound	48.00	0.00	386.67	160.00	1170.00	145.00	386.67
Westbound	24.00	32.00	0.00	100.00	246.00	0.00	32.00
Marina Lane to IL 26							
Eastbound	320.00	32.00	106.67	880.00	2088.00	40.00	138.67
Westbound	197.33	160.00	0.00	620.00	1548.00	0.00	160.00
IL 26 to Ten Mile Creek / Fauber Lane							
Eastbound	16.00	32.00	0.00	80.00	204.00	0.00	32.00
Westbound	77.33	90.67	0.00	380.00	942.00	0.00	90.67
Ten Mile Creek / Fauber Lane to County Line							
Eastbound	200.00	0.00	0.00	480.00	1026.00	0.00	0.00
Westbound	213.33	0.00	0.00	520.00	1104.00	0.00	0.00
TAZEWELL COUNTY SUB TOTAL							
	2099.00	640.00	1362.00	5960.00	16502.00	500.00	2002.00
County Line to Far Hills Drive							
Eastbound	469.33	32.00	0.00	1180.00	2544.00	0.00	32.00
Westbound	618.67	32.00	0.00	1540.00	3360.00	0.00	32.00
Far Hills Drive to Woodland Knols Drive							
Eastbound	162.67	0.00	0.00	380.00	822.00	0.00	0.00
Westbound	80.00	0.00	0.00	200.00	420.00	0.00	0.00
Woodland Knolls Drive / Upper Ten Mile Creek Rd to End of Project							
Eastbound	338.67	0.00	0.00	760.00	1674.00	0.00	0.00
Westbound	168.00	0.00	0.00	420.00	882.00	500.00	0.00
WOODFORD COUNTY SUB TOTAL							
	1837.00	64.00	0.00	4480.00	9702.00	500.00	64.00
TOTAL							
	3936.00	704.00	1362.00	10440.00	26204.00	1000.00	2066.00

FILE NAME = 11116.dgn	USER NAME = hudeisonne	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
673	**	TAZE/WOOD	60	24
CONTRACT NO. 68920				
ILLINOIS FED. AID PROJECT				

** 101RS-3; 102RS-4; 103RS-4; 104RS-7