

SUMMARY OF QUANTITIES

MARSHALL COUNTY

WOODFORD COUNTY

CONSTRUCTION CODE

CONSTRUCTION CODE

80/20 FED/ST

CODE	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY 1000 RURAL	ROADWAY 1000 RURAL
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	98	2	96
40600300	AGGREGATE (PRIME COAT)	TON	557	14	543
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL 4.75, N50	TON	6,946	195	6,751
40600895	CONSTRUCTING TEST STRIP	EACH	1		1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,817	87	4,730
40600990	TEMPORARY RAMP	SQ YD	1,093	14	1,079
40603305	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N30	TON	2,066		2,066
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	13,924	391	13,533
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	969	46	923
44000152	HOT-MIX ASPHALT SURFACE REMOVAL, 3/4"	SQ YD	166,159	4,550	161,609
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	17,030		17,030
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	4,206		4,206
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	1,138		1,138
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SQ YD	2,918		2,918
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	85,896	1,575	84,321
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3,438	99	3,339
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,056		1,056

REV