TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL WIDTH	LENGTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HOT-MIX ASPHALT SURFACE REMOVAL 0.75 IN	HOT-MIX ASPHALT SURFACE REMOVAL 2.0 IN	POL. BITUMINOUS MATERIALS PRIME COAT	AGGREGATE (PRIME COAT)	POL. LEVELING BINDER (MM) 0.75 IN	INCIDENTAL HOT-MIX ASPHALT SURFACING	HOT-MIX ASPHALT SURFACE CSE MIX D, N50 1.5 IN	HOT-MIX ASPHALT SURFACE COURSE MIX C, N30 BITUMINOUS SHOULDERS			
													LEFT AREA	LEFT SIDE	RIGHT AREA	RIGHT SIDE
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	TON	SQ YD	TON	SQ YD	TON
STA. 461 + 07 TO 461 + 37	26.00	30.00	86.67	86.67	14.44			0.05	0.26	3.65		7.32				
STA. 461 + 37 TO 477 + 12	26.00	1,575.00	4,550.00			4,550.00		2.37	13.65	191.56		384.04				
STA. 477 + 12 TO 490 + 65	26.00	1,353.00	3,908.67			3,908.67		2.03	11.73	164.56		329.91				
STA. 490 + 65 TO 503 + 80	27.00	1,315.00	3,945.00				3,945.00	2.05	11.84	166.07		332.91				
STA. 503 + 80 TO 512 + 25	32.00	845.00	3,004.44				3,044.44	1.56	9.01	126.43		253.36				
STA. 512 + 25 TO 519 + 62	27.00	737.00	2,211.00				2,211.00	1.15	6.63	93.08		186.58				
BRIDGE OMISSION STA 519+62 to STA 523+13																
STA. 523 + 13 TO 534 + 48	27.00	1,135.00	3,405.00				3,405.00	1.77	10.22	143.34		287.34				
STA. 534 + 48 TO 556 + 19	26.00	2,171.00	6,271.78			6,271.78		3.26	18.82	264.05		529.36				
STA EQ 556+19 (BK) = 50+93 (AH)																
STA. 50 + 93 TO 202 + 88	26.00	15,195.00	43,896.67			43,896.67		22.83	131.69	1,848.09		3,705.05				
STA. 202 + 88 TO 203 + 93	26.00	105.00	303.33			361.67		0.18	1.03	12.77		25.60			58.33	7.49
STA. 203 + 93 TO 208 + 38	26.00	445.00	1,285.56			1,780.00		0.87	4.85	54.12		108.51	247.22	31.73	247.22	31.73
STA. 208 + 38 TO 208 + 68	26.00	30.00	86.67	86.67	14.44			0.60	0.33	3.65		7.32	16.67	2.14	16.67	2.14
BRIDGE OMISSION STA 208+68 to STA 209+34																
STA. 209 + 34 TO 209 + 64	26.00	30.00	86.67	86.67	14.44			0.06	0.33	3.65		7.32	16.67	2.14	16.67	2.14
STA. 209 + 64 TO 240 + 65	26.00	3,100.50	8,957.00			12,402.00		6.04	33.76	377.10		756.01	1,722.50	221.10	1,722.50	221.10
STA. 240 + 65 TO 240 + 95	26.00	30.00	86.67	86.67	14.44			0.06	0.33	3.65		7.32	16.67	2.14	16.67	2.14
BRIDGE OMISSION STA 240+95 to STA 241+82																
STA. 241 + 82 TO 242 + 12	26.00	30.00	86.67	86.67	14.44			0.06	0.33	3.65		7.32	16.67	2.14	16.67	2.14
STA. 242 + 12 TO 339 + 86	26.00	9,774.00	28,236.00			39,096.00		19.03	106.43	1,188.76		2,383.23	5,430.00	697.01	5,430.00	697.01
STA. 339 + 86 TO 370 + 61	26.00	3,075.00	8,883.33			8,883.33		4.62	26.65	374.00		749.79				
STA. 370 + 61 TO 370 + 91	26.00	30.00	86.67	86.67	14.44			0.05	0.26	3.65		7.32				
BRIDGE OMISSION STA 370+91 to STA 371+17																
STA. 371 + 17 TO 371 + 47	26.00	30.00	86.67	86.67	14.44			0.05	0.26	3.65		7.32				
STA. 371 + 47 TO 456 + 53	26.00	8,506.00	24,572.89			24,572.89		12.78	73.72	1,034.54		2,074.05				
STA. 456 + 53 TO 463 + 60	26.00	707.00	2,042.44			3,142.22		1.50	8.33	85.99		172.39	549.89	70.21	549.89	70.21
STA. 463 + 60 TO 463 + 66	26.00	6.00	17.33			22.00		0.01	0.06	0.73		1.46			4.67	0.60
STA. 463 + 66 TO 513 + 40	26.00	4,974.00	14,369.33			14,369.33		7.47	43.11	604.96		1,212.83				
STA. 513 + 40 TO 528 + 15	27.00	1,475.00	4,425.00				4,425.00	2.30	13.28	186.28		373.42				
STA. 528 + 15 TO 528 + 45	26.00	30.00	86.67	86.67	14.44			0.05	0.26	3.65		7.32				
SUB-TOTAL				**693**	**116**	**163,257**	**17,030**	**93**	**527**	**6,946**	**0**	**13,924**	**8,016**	**1,029**	**8,079**	**1,037**

PRIME COAT CONVERSION FACTORS

SURFACE TYPE	BIT PR COAT (GAL/SQ YD)	AGG PR COAT (LB/SQ YD)
COLD MILLED SURFACES	0.1	4
EXISTING PAVEMENT	0.05	4
NEW BITUMINOUS COURSES	0.03	2

BITUMINOUS & AGGREGATE CONVERSION FACTORS

SURFACE TYPE	
BIT. SURF. COURSES	112 LB /SQ YD/IN
ALL OTHER BIT.	112 LB /SQ YD/IN
AGGREGATE SHOULDERS	2.05 TONS/CUYD