

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL WIDTH FT	LENGTH FT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT SQ YD	TEMPORARY RAMP SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL 0.75 IN SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL 2.0 IN SQ YD	POL. BITUMINOUS MATERIALS PRIME COAT TON	AGGREGATE (PRIME COAT) TON	POL. LEVELING BINDER (MM) 0.75 IN TON	INCIDENTAL HOT-MIX ASPHALT SURFACING	HOT-MIX ASPHALT SURFACE CSE MIX D, N50 1.5 IN TON	HOT-MIX ASPHALT SURFACE COURSE MIX C, N30					
													BITUMINOUS SHOULDERS					
													LEFT AREA SQ YD	LEFT SIDE TON	RIGHT AREA SQ YD	RIGHT SIDE TON		
SIDE ROADS																		
2300 N RD		12.00	349.64	349.64	143.89			0.18	1.05		36.71							
MADISON ST (1)		21.00	104.47	104.47	13.33			0.05	0.31		10.97							
STATE ST (1)		109.00	169.39	63.11	15.89	106.28		0.09	0.51		17.79							
JEFFERSON ST		131.00	252.08	82.46	17.50	169.62		0.13	0.76		26.47							
WOODFORD ST (1)		21.00	69.12	64.35	11.67	4.77		0.04	0.21		7.26							
WOODFORD ST (2)		17.00	52.40	52.40	11.39			0.03	0.16		5.50							
WATER ST (1)		18.00	68.90	68.90	16.67			0.04	0.21		7.23							
WATER ST (2)		18.00	53.81	53.81	10.56			0.03	0.16		5.65							
CHURCH ST (1)		19.00	79.33	79.33	16.67			0.04	0.24		8.33							
CHURCH ST (2)		19.50	60.89	60.89	11.39			0.03	0.18		6.39							
MAGNOLIA ST (1)		13.00	42.91	42.91	11.39			0.02	0.13		4.51							
MAGNOLIA ST (2)		24.50	79.10	58.82	11.67	20.27		0.04	0.24		8.31							
CHESNUT ST (1)		23.50	71.99	58.52	12.78	14.14		0.04	0.22		7.56							
CHESNUT ST (2)		24.00	85.76	71.11	17.78	14.65		0.04	0.26		9.01							
WALNUT ST (1)		27.00	111.19	82.22	20.56	28.97		0.06	0.33		11.68							
WALNUT ST (2)		10.50	41.28	41.28	16.67			0.02	0.12		4.33							
MADISON ST (2)		5.00	42.52	42.52	22.23			0.02	0.13		4.46							
MAPLE ST		12.00	109.82	109.82	33.06			0.06	0.33		11.53							
PARKSIDE RD		5.00	49.54	49.54	26.17			0.03	0.15		5.20							
MEMORIAL PARK		5.00	26.29	26.29	12.47			0.01	0.08		2.76							
PARKVIEW CIR (1)		24.50	70.98	51.26	9.44	19.72		0.04	0.21		7.45							
PARKVIEW CIR (2)		18.50	63.49	63.49	10.56			0.03	0.19		6.67							
MAIN ST (1)		41.00	172.37	59.99	13.33	112.38		0.09	0.52		18.10							
HILCREST ST		24.50	84.97	60.69	10.28	24.28		0.04	0.25		8.92							
SNIDER COURT		47.00	226.47	60.01	12.50	166.45		0.12	0.68		23.78							
2200 N RD		22.00	103.47	87.55	13.33	15.91		0.05	0.31		10.86							
2100 N RD (1)		26.50	118.83	73.15	11.67	45.68		0.06	0.36		12.48							
2100 N RD (2)		29.00	116.87	63.71	11.67	53.16		0.06	0.35		12.27							
CLARK ST (1)		53.00	493.18	112.65	23.33	380.53		0.26	1.48		51.78							
CLARK ST (2)		41.00	242.69	73.77	14.44	168.92		0.13	0.73		25.48							
BANTA RD		42.50	217.91	67.37	13.89	150.54		0.11	0.65		22.88							
STATE ST (2)		26.00	304.19	224.36	51.67	79.82		0.16	0.91		31.94							
MAIN ST (2)		34.00	167.41	66.92	12.22	100.49		0.09	0.50		17.58							
MAIN ST (3)		30.00	160.52	81.30	14.17	79.22		0.08	0.48		16.85							
BLACK PARTRIDGE (1)		29.00	96.32	53.99	10.56	42.33		0.05	0.29		10.11							
BLACK PARTRIDGE (2)		35.00	184.90	71.21	12.78	113.69		0.10	0.55		19.41							
1675 N RD (1)		19.00	77.88	77.88	16.11			0.04	0.23		8.18							
1675 N RD (2)		33.00	154.35	61.64	10.56	92.71		0.08	0.46		16.21							
1600 N RD (1)		35.00	193.29	72.26	13.89	121.03		0.10	0.58		20.30							
1600 N RD (2)		26.00	128.82	80.95	13.89	47.87		0.07	0.39		13.53							
1500 N RD (1)		36.00	158.07	62.66	13.89	95.41		0.08	0.47		16.60							
1500 N RD (2)		31.00	141.96	75.26	16.11	66.71		0.07	0.43		14.91							
WEIDMAN ST		24.00	280.00	226.82	52.22	53.18		0.15	0.84		29.40							
MADISON ST (3)		31.00	160.71	81.42	16.67	79.29		0.08	0.48		16.87							
MADISON ST (4)		32.50	179.88	81.23	16.11	98.65		0.09	0.54		18.89							
MONROE ST (1)		31.50	159.68	79.54	16.67	80.15		0.08	0.48		16.77							
MONROE ST (2)		30.00	154.80	82.25	16.67	72.55		0.08	0.46		16.25							
CHATHAM ST (1)		36.00	167.01	64.16	13.33	102.85		0.09	0.50		17.54							
CHATHAM ST (2)		31.00	161.80	81.54	16.67	80.26		0.08	0.49		16.99							
PARTRIDGE ST (1)		7.50	65.33	65.33	27.22			0.03	0.20		6.86							
PARTRIDGE ST (2)		16.50	96.69	96.69	18.33			0.05	0.29		10.15							
ENTRANCES																		
C.E. & P.E. (44 TOTAL)			1,726.83					0.90	5.18		86.29							
MAILBOX TURNOUTS (7 TOTAL)			565.56					0.29	1.70		71.26							
MAILBOX TURNOUTS + ENTRANCE (9 TOTAL)			589.40					0.31	1.77		74.26							
SUB-TOTAL				4,123	978	2,902	0	5	30	0	969	0	0	0	0			
SUB-TOTAL (FROM SHEET 1)				693	116	163,257	17,030	93	527	6,946	0	13,924	8,016	1,029	8,079	1,037		
GRAND-TOTAL				4,817	1,093	166,159	17,030	98	557	6,946	969	13,924	8,016	1,029	8,079	1,037		
													TOTAL		16,096		2,066	