

ROUTE		SECTION	COUNTY	SHEET	
F.A.P.	669	15RS-6;(14,13,11R) RS-4;(10R)RS-7	PEORIA	TOTAL	NO.
MKD.	IL 116			65	30

TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH	LENGTH	AREA	HOT-MIX ASPHALT SURFACE REMOVAL BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL 0.75 IN	HMA SURFACE REMOVAL 1.5 IN	POLYMERIZED BITUMINOUS MATERIALS PRIME COAT	AGGREGATE (PRIME COAT)	HOT-MIX-ASPHALT SURFACE COURSE MIX E, N50 1.5 IN	INCIDENTAL HOT-MIX ASPHALT SURFACING 1.5 IN	HOT-MIX ASPHALT SURFACE COURSE MIX C, N50 HMA SHOULDERS		AGGREGATE SHOULDERS TYPE B	
	FT	FT	SQ YD	SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	TON	LEFT SIDE TON	RIGHT SIDE TON	LEFT SIDE TON	RIGHT SIDE TON
FARMINGTON RD TO EDENS RD															
STATION EQUATION															
STA. 515 + 05 TO 516 + 80	42.00	175.29	818.02			818.02		0.33	1.64	68.92		9.92	9.92	4.16	4.16
STA. 516 + 80 TO 533 + 05	36.00	1625.00	6500.00			6500.00		2.60	13.00	547.90		91.95	91.95	38.56	38.56
STA. 533 + 05 TO 536 + 55	43.00	350.00	1672.22			1672.22		0.67	3.34	140.88		19.80	19.80	8.30	8.30
STA. 536 + 55 TO 543 + 70	50.00	715.00	3972.22			3972.22		1.59	7.94	334.50		40.46	40.46	16.96	16.96
STA. 543 + 70 TO 547 + 20	43.00	350.00	1672.22			1672.22		0.67	3.34	140.88		19.80	19.80	8.30	8.30
STA. 547 + 20 TO 647 + 38	36.00	10018.00	40072.00			40072.00		16.03	80.14	3377.74		566.85	566.85	237.70	237.70
STA. 647 + 38 TO 672 + 67	40.00	2529.00	11240.00				11240.00	4.50	22.48	947.11					
STA. 672 + 67 TO 678 + 88	42.00	621.00	2898.00				2898.00	1.16	5.80	244.16					
STA. 678 + 88 TO 682 + 37	40.00	348.83	1550.36				1550.36	0.62	3.10	130.64					
STATION EQUATION															
STA. 682 + 56 TO 689 + 50	40.00	694.17	3085.20				3085.20	1.23	6.17	259.97					
STA. 689 + 50 TO 694 + 45	47.00	495.00	2585.00			2585.00		1.03	5.17	217.72		14.15	37.25	11.74	11.74
STA. 694 + 45 TO 699 + 14	42.00	469.00	2188.67			2188.67		0.88	4.38	184.40		13.41	13.41	11.13	11.13
STA. 699 + 14 TO 702 + 06	36.00	292.00	1168.00			1168.00		0.47	2.34	98.45		8.35	8.35	6.93	6.93
STA. 702 + 06 TO 743 + 72	30.00	4166.29	13887.63			13887.63		5.56	27.78	1171.42		119.09	119.09	98.85	98.85
STATION EQUATION															
STA. 743 + 81 TO 781 + 85	30.00	3803.74	12679.13			12679.13		5.07	25.36	1069.48		108.72	108.72	90.25	90.25
STA. 781 + 85 TO 782 + 15	30.00	30.00	100.00	100.00	13.33			0.04	0.20	8.44		0.86	0.86	0.71	0.71
RIGHT TURN LANES															
EB TAYLOR RD	VAR	372.00	390.89			390.89		0.16	0.78	33.27					
EB FARMINGTON RD	VAR	310.00	309.45			309.45		0.12	0.62	26.36					
SIDEROADS															
TAYLOR RD	VAR	35.00	210.00	43.33	6.67	152.78		0.08	0.42		17.68				
HALL RD	VAR	40.00	226.67	28.89	6.67	173.33		0.09	0.45		19.09				
GREENGOLD RD	VAR	36.00	192.00	30.00	6.67	141.56		0.08	0.38		16.17				
PINKERTON RD	VAR	40.00	200.00	28.89	6.67	153.33		0.08	0.40		16.85				
N MURPHY RD	VAR	32.00	135.11	27.78	6.67		95.33	0.05	0.27		11.39				
S MURPHY RD	VAR	32.00	147.55	26.67	6.67		103.89	0.06	0.30		12.43				
CAROLE AVE	VAR	25.00	102.77	27.78	6.67		63.33	0.04	0.21		8.66				
LAKESHORE DR	VAR	36.00	166.00	26.67	6.67		122.78	0.07	0.33		13.99				
LUELLYN PL	VAR	30.00	131.67	27.78	6.67		90.00	0.05	0.26		11.10				
BALAGNA CT	VAR	35.00	208.06	31.11	6.67		151.39	0.08	0.42		17.52				
N RUNKLE ST	VAR	34.00	151.11	28.89	6.67		109.33	0.06	0.30		12.73				
S RUNKLE ST	VAR	36.00	170.00	28.89	6.67		125.67	0.07	0.34		14.32				
N MAIN ST	VAR	20.00	144.44	67.78	6.67		73.33	0.06	0.29		12.16				
S MAIN ST	VAR	25.00	159.72	51.11	6.67		98.00	0.06	0.32		13.45				
N FIRST ST	VAR	33.00	143.00	26.67	6.67		102.22	0.06	0.29		12.05				
S FIRST ST	VAR	30.00	131.67	27.78	6.67		90.00	0.05	0.26		11.10				
N SECOND ST	VAR	36.00	162.00	27.78	6.67		119.89	0.06	0.32		13.65				
S SECOND ST	VAR	32.00	145.77	25.56	6.67		102.67	0.06	0.29		12.28				
N THIRD ST	VAR	27.00	130.50	31.11	6.67		84.06	0.05	0.26		10.99				
S THIRD ST	VAR	31.00	142.94	28.89	6.67		99.17	0.06	0.29		12.04				
N ALLEY	VAR	23.00	57.50	14.44	6.67		33.94	0.02	0.12		4.86				
S ALLEY	VAR	21.00	54.83	15.56	6.67		29.94	0.02	0.11		4.63				
N HANNA CITY - GLASFORD RD	VAR	50.00	261.11	34.44	6.67		213.33	0.10	0.52		21.99				
S HANNA CITY - GLASFORD RD	VAR	50.00	352.78	42.22	6.67		286.67	0.14	0.71		29.69				
MALISTER RD	VAR	52.00	300.44	28.89	6.67	306.22		0.12	0.60		25.30				
CONN RD	VAR	50.00	272.22	26.67	6.67	277.78		0.11	0.54		22.92				
GRAND-TOTAL (SHEET 1)				906	187	89,120	20,969	45	223	9,002	379	1,013	1,036	534	534
												TOTAL	2050	TOTAL	1067

SCHEDULE OF QUANTITIES
IL 116