

SUMMARY OF QUANTITIES (SHEET 1 OF 3)

URBAN
80/20 FED/ST

LOCATION OF WORK: FAP ROUTE 709 (US 136)
CHAMPAIGN COUNTY
ROADWAY IMPROVEMENTS
STA. 2270+54.60 - STA. 105+64.00
URBAN MULTILANE

FUNDING BREAKOUT:
CONSTRUCTION TYPE CODE: 1000-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6,410.0
40600300	AGGREGATE (PRIME COAT)	TON	193.0
40600845	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N90	TON	3,370.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT- MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	SQ YD	4,175.0
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL- BUTT JOINT	SQ YD	1,530.0
40600990	TEMPORARY RAMP	SQ YD	360.0
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	5,600.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	955.0
40800030	AGGREGATE (PRIME COAT)	TON	15.0
40800050	INCIDENTAL HOT- MIX ASPHALT SURFACING	TON	510.0
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	44,520.0
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	18.0
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	33.0
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	722.0
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	39.0
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	454.0
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	47.0
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	15.0

FILE NAME *	USER NAME = hoganbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\p\work\PWIDOT\HOGANBJ\0104446\0574117-sht-500.dgn	DRAWN -	REVISED -	709					(113)RS-1	CHAMPAIGN	65	4	
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	SCALE: N/A			SHEET NO. 1 OF 3 SHEETS			STA. _____ TO STA. _____			
PLOT DATE = 1/29/2010	DATE -	REVISED -	FED. ROAD DIST. NO. -			ILLINOIS FED. AID PROJECT			CONTRACT NO. 70117			