

CLASS "D" PATCHING

PATCH NUMBER	STATION	DIRECTION	LANE	LENGTH	WIDTH	CLASS "D"	CLASS "D"	CLASS "D"
						PATCHES	PATCHES	PATCHES
				(ft)	(ft)	TYPE II, 16"	TYPE III, 16"	TYPE IV, 16"
						SQ YD	SQ YD	SQ YD
						44201839	44201843	44201845
1	3019+84	NB	PL	6	12	8.00		
2	3019+84	NB	DL	6	12	8.00		
3	3019+84	BI-DIR		6	14	9.33		
4	3019+84	SB	PL	6	12	8.00		
5	3019+84	SB	DL	6	12	8.00		
6	3018+88	NB	PL	6	12	8.00		
7	3018+88	NB	DL	6	12	8.00		
8	3018+88	BI-DIR		6	14	9.33		
9	3018+88	SB	PL	6	12	8.00		
10	3018+88	SB	DL	6	12	8.00		
11	3018+64	SB	PL	6	12	8.00		
12	3018+64	SB	DL	6	12	8.00		
13	3018+46	NB	PL	6	12	8.00		
14	3018+46	NB	DL	6	12	8.00		
15	3018+46	BI-DIR		6	14	9.33		
16	3018+46	SB	PL	6	12	8.00		
17	3018+46	SB	DL	6	12	8.00		
18	3017+83	NB	PL	6	12	8.00		
19	3017+83	NB	DL	6	12	8.00		
20	3017+83	BI-DIR		6	14	9.33		
21	3017+83	SB	PL	6	12	8.00		
22	3017+83	SB	DL	6	12	8.00		
23	3017+61	NB	PL	6	12	8.00		
24	3017+61	NB	DL	6	12	8.00		
25	3017+44	NB	PL	6	12	8.00		
26	3017+44	NB	DL	6	12	8.00		
27	3016+08	SB	PL	6	12	8.00		
28	3016+08	SB	DL	6	12	8.00		
29	3015+82	SB	PL	30	12			40.00
30	2999+12	NB	PL	6	12	8.00		
31	2998+73	NB	DL	16	12		21.33	
32	2992+76	NB	PL	6	12	8.00		
33	2987+98	NB	PL	6	12	8.00		
34	2987+98	NB	DL	6	12	8.00		
35	2987+98	BI-DIR		6	14	9.33		
36	2987+98	SB	PL	6	12	8.00		
37	2987+98	SB	DL	6	12	8.00		
38	2981+05	NB	PL	6	12	8.00		
39	2981+05	NB	DL	6	12	8.00		
40	2981+05	BI-DIR		6	14	9.33		
41	2981+05	SB	PL	6	12	8.00		
42	2981+05	SB	DL	6	12	8.00		
43	2928+51	NB	PL	6	12	8.00		
44	2928+51	NB	DL	6	12	8.00		
45	2928+51	BI-DIR		6	14	9.33		
46	2928+51	SB	PL	6	12	8.00		
47	2928+51	SB	DL	6	12	8.00		
48	2923+23	NB	PL	6	12	8.00		
49	2923+23	NB	DL	6	12	8.00		
50	2923+23	BI-DIR		6	14	9.33		
51	2923+13	SB	PL	6	12	8.00		

CLASS "D" PATCHING (CONT)

52	2923+13	SB	DL	6	12	8.00			
53	2922+35	NB	PL	6	12	8.00			
54	2922+35	NB	DL	6	12	8.00			
55	2922+35	BI-DIR		6	14	9.33			
56	2922+35	SB	PL	6	12	8.00			
57	2922+35	SB	DL	6	12	8.00			
58	2915+02	NB	PL	6	12	8.00			
59	2915+02	NB	DL	6	12	8.00			
60	2915+02	BI-DIR		6	14	9.33			
61	2915+02	SB	PL	6	12	8.00			
62	2915+02	SB	DL	6	12	8.00			
63	2912+49	NB	DL	6	16	10.67			
						TOTAL	496.00	21.33	40.00
						USE	496	22	40

HOT MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH (SHOULDERS)
(44000198)

LANE	STATION	TO	STATION	LENGTH (FEET)	WIDTH (FEET)	AREA (SQ. YD)	HOT-MIX ASPHALT SURF. REMOVAL VAR. DEP.
							(SQYD)
SB SHLDR	2911+70		2936+28	2,458.00	4.00	1,092.44	1,092.44
SB SHLDR	2938+54		2946+00	746.00	4.00	331.56	331.56
SB SHLDR	2949+18		2953+59	441.00	4.00	196.00	196.00
SB SHLDR	2955+84		2960+66	482.00	4.00	214.22	214.22
SB SHLDR	2962+91		2987+41	2,450.00	4.00	1,088.89	1,088.89
SB SHLDR	2989+89		2994+34	445.00	4.00	197.78	197.78
SB SHLDR	2996+36		3002+01	565.00	4.00	251.11	251.11
SB SHLDR	3004+32		3007+91	359.00	4.00	159.56	159.56
SB SHLDR	3009+70		3026+30	1,660.00	4.00	737.78	737.78
NB SHLDR	2911+70		2937+10	2,540.00	4.00	1,128.89	1,128.89
NB SHLDR	2939+03		2947+01	798.00	4.00	354.67	354.67
NB SHLDR	2949+86		2953+80	394.00	4.00	175.11	175.11
NB SHLDR	2955+84		2960+30	446.00	4.00	198.22	198.22
NB SHLDR	2962+22		2987+94	2,572.00	4.00	1,143.11	1,143.11
NB SHLDR	2990+89		2995+05	416.00	4.00	184.89	184.89
NB SHLDR	2997+26		3001+75	449.00	4.00	199.56	199.56
NB SHLDR	3003+97		3008+47	450.00	4.00	200.00	200.00
NB SHLDR	3010+52		3018+61	809.00	4.00	359.56	359.56
NB SHLDR	3021+82		3026+30	1,025.00	4.00	455.56	455.56
SUB-TOTAL						8,184.44	8,668.89
USE							8,669.00

FILE NAME =	USER NAME = leroyma	DESIGNED -	REVISED -
c:\pwork\pwork\PWIDOT\LEROYMA\d0144976\d9505300.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/29/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	4TR5-9	VERMILION	25	9
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 70123	