

LOCATION OF WORK:

FAP 332 (IL 1/ US 136)  
VERMILION COUNTY  
STA. 62+23.58 TO  
STA. 209+54.04  
URBAN  
100% STATE

FAP 332 (IL 1/ US 136)  
VERMILION COUNTY  
STA. 209+54.04  
STA. 769+25.00  
RURAL  
100% STATE

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	24,461.0	7876.0	16585.0
40600300	AGGREGATE (PRIME COAT)	TON	490.0	170.0	320.0
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	6,761.0	822.0	5839.0
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	2,416.0	2416.0	0.0
40600895	CONSTRUCTING TEST STRIP	EACH	4.0	2.0	2.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	11,802.0	3950.0	7852.0
40600990	TEMPORARY RAMP	SQ YD	550.0	250.0	300.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	13,522.0	1644.0	11878.00
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4,831.0	4831.0	0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1,181.0	395.0	786.0
40800030	AGGREGATE (PRIME COAT)	TON	24.0	8.0	16.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	992.0	332.0	660.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	52,240.0	13488.0	38752.0
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	218,484.0	77078.0	141406.0
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	836.0	0.0	836.0
44201819	CLASS D PATCHES, TYPE III, 14 INCH	SQ YD	109.0	0.0	109.00
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SQ YD	1,299.0	810.0	489.0
44201869	CLASS D PATCHES, TYPE IV, 18 INCH	SQ YD	54.0	54.0	0.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1,602.0	91.0	1511.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4,389.0	1133.0	3256.0
56109210	WATER VALVES TO BE ADJUSTED	EACH	16.0	16.0	0.0
60255500	MANHOLES TO BE ADJUSTED	EACH	41.0	41.0	0.0
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	1.0	1.0	0.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6.0	1.0	5.0
67100100	MOBILIZATION	L SUM	1.0	0.2	0.8
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.0	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.0	1.0
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1.0	1.0	0.0

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				*48-X1RS&48-X2,RX,RX-1RS-1	
ca:\pr_work\p\dot\bowerml\d0145216\70124	S00.dgn	DRAWN - MLB	REVISED -		F.A.P. RTE. 332	SECTION *	COUNTY VERMILION	TOTAL SHEETS 86	SHEET NO. 5	CONTRACT NO. 70124
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	
	PLOT DATE = 1/27/2010	DATE - 08-20-2009	REVISED -							