

LOCATION OF WORK:

FAP 332 (IL 1/ US 136)
VERMILION COUNTY
STA. 62+23.58 TO
STA. 209+54.04
URBAN
100% STATE

FAP 332 (IL 1/ US 136)
VERMILION COUNTY
STA. 209+54.04
STA. 769+25.00
RURAL
100% STATE

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

CODE NO	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0	1.0	0.0
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0	0.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	44,170.0	18268.0	25902.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	192,936.0	51716.0	141220.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1,103.0	1103.0	0.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,896.0	1896.0	0.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	519.0	519.0	0.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	4,909.0	2030.0	2879.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,337.0	1337.0	0.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	65,289.0	41115.0	24174.0
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,103.0	1103.0	0.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,896.0	1896.0	0.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	519.0	519.0	0.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	127,647.0	10601.0	117046.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,658.0	741.0	917.0
* 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,658.0	741.0	917.0
81400115	HANDHOLE TO BE ADJUSTED	EACH	2.0	2.0	0.0
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1,785.0	1785.0	0.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	14.0	7.0	7.0
Z0048400	RAILROAD CROSSING REMOVAL	EACH	1.0	0.0	1.0
Z0055300	RUMBLE STRIP	EACH	9.0	0.0	9.0

*SPECIALTY ITEMS

*(48-X1)RS&(48-X2,RX,RX-1)RS-1

FILE NAME = c:\pwork\pwork\boverml\d0145216\70124	USER NAME = boverml 500.dgn	DESIGNED - MLB DRAWN - MLB	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE. 332	SECTION *	COUNTY VERMILION	TOTAL SHEETS 86	SHEET NO. 6	
PLOT SCALE = 40.0000' / IN.					SCALE:				SHEET NO. OF SHEETS		STA. TO STA.		CONTRACT NO. 70124	
PLOT DATE = 1/27/2010					DATE - 08-20-2009				ILLINOIS FED. AID PROJECT					