

INCIDENTAL SCHEDULE									
LOCATION	AREA (As-Builts & CADD)	40800050 - Incidental HMA Surface					40600982 HMA	40800010 Bit.	40800030 Agg.
		Private	Field	Commercial	Mailbox	Side Roads	Surf. Rem., Bt. Jt.	Mtls. (Prime Coat)	(Prime Coat)
		Entrance	Entrance	Entrance	Turnouts		SQ YD	GAL	TON
	SQ YD	TON	TON	TON	TON	TON			
RT STA 257+22 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 257+44 P.E.	33.3	2.8					33.3	3.3	0.07
LT STA 258+05 P.E.	36.7	3.1					36.7	3.7	0.07
LT STA 258+36 P.E.	44.4	3.7					44.4	4.4	0.09
RT STA 259+97 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 260+25 P.E.	44.4	3.7					44.4	4.4	0.09
LT STA 260+60 P.E.	25.0	2.1					25.0	2.5	0.05
RT STA 261+18 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 261+40 P.E.	31.1	2.6					31.1	3.1	0.06
RT STA 262+40 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 262+62 P.E.	32.2	2.7					32.2	3.2	0.06
RT STA 265+90 P.E.	31.1	2.6					31.1	3.1	0.06
RT STA 266+12 MBTO	10.4				0.9		10.4	1.0	0.02
RT STA 267+10 P.E.	36.7	3.1					36.7	3.7	0.07
RT STA 267+61 TR 2550	171.0					14.4	171.0	17.1	0.34
LT STA 267+72 TR 2550	176.0					14.8	176.0	17.6	0.35
RT STA 274+20 P.E.	26.0	2.2					26.0	2.6	0.05
RT STA 278+01 F.E.	12.5		1.1				12.5	1.3	0.03
LT STA 278+16 P.E.	31.1	2.6					31.1	3.1	0.06
LT STA 280+74 P.E.	40.0	3.4					40.0	4.0	0.08
RT STA 280+88 MBTO	15.2				1.3		15.2	1.5	0.03
RT STA 281+49 P.E.	36.7	3.1					36.7	3.7	0.07
RT STA 282+44 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 282+66 P.E.	31.1	2.6					31.1	3.1	0.06
RT STA 283+78 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 284+00 P.E.	31.1	2.6					31.1	3.1	0.06
RT STA 290+89 P.E.	44.4	3.7					44.4	4.4	0.09
RT STA 293+14 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 293+36 P.E.	31.1	2.6					31.1	3.1	0.06
LT STA 294+09 P.E.	32.2	2.7					32.2	3.2	0.06
LT STA 303+95 P.E.	34.4	2.9					34.4	3.4	0.07
RT STA 304+01 MBTO	15.2				1.3		15.2	1.5	0.03
LT STA 313+18 F.E.	12.7		1.1				12.7	1.3	0.03
RT STA 314+22 F.E.	12.7		1.1				12.7	1.3	0.03
RT STA 320+96 TR 2650	127.0					10.7	127.0	12.7	0.25
LT STA 321+03 TR 2650	127.0					10.7	127.0	12.7	0.25
RT STA 324+59 MBTO	31.1				2.6		31.1	3.1	0.06
RT STA 324+81 P.E.	31.1	2.6					31.1	3.1	0.06
RT STA 342+43 F.E.	12.7		1.1				12.7	1.3	0.03
RT STA 344+66 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 344+88 P.E.	31.1	2.6					31.1	3.1	0.06
<b>PAGE TOTAL</b>		<b>60.1</b>	<b>4.3</b>	<b>0.0</b>	<b>13.9</b>	<b>50.5</b>	<b>1532.3</b>	<b>153.2</b>	<b>3.1</b>

\*(48-X1)RS&(48-X2,RX,RX-1)RS-1

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\p\dot\bowerm\00145216\70124	Schedule.dgn	DRAWN - MLB	REVISED -					332	*	VERMILION	86	32
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT			
	PLOT DATE = 1/26/2010	DATE - 08-20-2009	REVISED -						CONTRACT NO. 70124			