

INCIDENTAL SCHEDULE									
LOCATION	AREA (As-Builts & CADD)	40800050 - Incidental HMA Surface					40600982 HMA Surf. Rem., Bt. Jt.	40800010 Bit. Mtls. (Prime Coat)	40800030 Agg. (Prime Coat)
		Private Entrance	Field Entrance	Commercial Entrance	Mailbox Turnouts	Side Roads			
		SQ YD	TON	TON	TON	TON			
RT STA 649+60 P.E.	31.1	2.6					31.1	3.1	0.06
LT STA 655+04 F.E.	12.7		1.1				12.7	1.3	0.03
RT STA 660+00 P.E.	32.2	2.7					32.2	3.2	0.06
LT STA 660+30 MBTO	15.2				1.3		15.2	1.5	0.03
LT STA 666+09 P.E.	36.7	3.1					36.7	3.7	0.07
LT STA 666+33 MBTO	11.7				1.0		11.7	1.2	0.02
LT STA 667+62 MBTO	10.5				0.9		10.5	1.1	0.02
LT STA 667+90 P.E.	34.4	2.9					34.4	3.4	0.07
LT STA 675+18 F.E.	13.3		1.1				13.3	1.3	0.03
RT STA 681+28 TR 3330	126.8					10.7	126.8	12.7	0.25
LT STA 681+29 MBTO	15.2				1.3		15.2	1.5	0.03
RT STA 694+42 F.E.	12.7		1.1				12.7	1.3	0.03
RT STA 711+84 F.E.	13.3		1.1				13.3	1.3	0.03
LT STA 713+04 TR 3390	126.8					10.7	126.8	12.7	0.25
RT STA 717+98 F.E.	13.3		1.1				13.3	1.3	0.03
LT STA 720+37 MBTO	10.5				0.9		10.5	1.1	0.02
LT STA 720+55 P.E.	12.7	1.1					12.7	1.3	0.03
RT STA 721+76 P.E.	31.1	2.6					31.1	3.1	0.06
LT STA 743+51 P.E.	40.0	3.4					40.0	4.0	0.08
LT STA 743+77 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 747+60 TR 3450	126.8					10.7	126.8	12.7	0.25
RT STA 754+15 F.E.	12.7		1.1				12.7	1.3	0.03
LT STA 760+76 F.E.	15.3		1.3				15.3	1.5	0.03
RT STA 761+06 C.E.	33.3			2.8			33.3	3.3	0.07
RT STA 762+00 MBTO	11.7				1.0		11.7	1.2	0.02
RT STA 762+23 C.E.	34.4			2.9			34.4	3.4	0.07
RT STA 763+10 C.E.	44.4			3.7			44.4	4.4	0.09
RT STA 765+17 C.E.	43.3			3.6			43.3	4.3	0.09
RT STA 767+00 C.E.	40.0			3.4			40.0	4.0	0.08
RT STA 768+16 P.E.	31.1	2.6					31.1	3.1	0.06
LT STA 768+27 MBTO	15.2				1.3		15.2	1.5	0.03
<b>PAGE TOTAL</b>		<b>20.9</b>	<b>7.8</b>	<b>16.4</b>	<b>8.5</b>	<b>32.0</b>	<b>1020.1</b>	<b>102.0</b>	<b>2.0</b>
<b>GRAND TOTAL</b>		<b>234.7</b>	<b>41.5</b>	<b>75.3</b>	<b>47.4</b>	<b>592.4</b>	<b>11801.6</b>	<b>1180.2</b>	<b>23.6</b>
<b>USE</b>				<b>992.0</b>			<b>11802.0</b>	<b>1181.0</b>	<b>24.0</b>

\*(48-X1)RS&(48-X2,RX,RX-1)RS-1

FILE NAME =	USER NAME = bowerml	DESIGNED -	MLB	REVISED -		<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw\work\p\dot\bowerml\d0145216\70124	Schedule.dgn	DRAWN -	MLB	REVISED -						332	*	VERMILION	86	35	
	PLOT SCALE = 40.0000' / IN.	CHECKED -		REVISED -			SCALE:			SHEET NO. OF SHEETS	STA.	TO STA.	CONTRACT NO. 70124		
	PLOT DATE = 1/26/2010	DATE -	08-20-2009	REVISED -			ILLINOIS FED. AID PROJECT								