

78000200 THERMOPLASTIC PAVEMENT MARKING LINE-4" (YELLOW)

	STATION	TO	STATION	FOOT		70300100 SHORT TERM PVT MARKINGS FOOT	70300220 TEMP PVT MK LINE 4" FOOT	70301000 WORK ZONE PVT MK REM SQ FT
	LT	62+23.58	68+90.00	666.4		199.9	666.4	22.2
	RT	62+23.58	68+90.00	666.4		199.9	666.4	22.2
	LT	68+90.00	70+20.00	280.0	(DOUBLE LINES)	78.0	260.0	8.7
	RT	71+20.00	72+50.00	280.0	(DOUBLE LINES)	78.0	260.0	8.7
	LT	72+50.00	78+90.00	640.0		192.0	640.0	21.3
	RT	72+50.00	78+90.00	640.0		192.0	640.0	21.3
	LT	79+94.00	93+54.00	1360.0		408.0	1360.0	45.3
	RT	79+94.00	93+54.00	1360.0		408.0	1360.0	45.3
	LT	93+54.00	95+67.00	426.0	(DOUBLE LINES)	127.8	426.0	14.2
	RT	96+79.00	98+27.00	296.0	(DOUBLE LINES)	88.8	296.0	9.9
	LT	98+27.00	110+52.00	1225.0		367.5	1225.0	40.8
	RT	98+27.00	110+52.00	1225.0		367.5	1225.0	40.8
	LT	111+56.00	112+06.00	50.0		15.0	50.0	1.7
	RT	111+56.00	112+06.00	50.0		15.0	50.0	1.7
	LT	113+15.00	116+45.00	330.0		99.0	330.0	11.0
	RT	113+15.00	116+45.00	330.0		99.0	330.0	11.0
	LT	117+52.00	122+62.00	510.0		153.0	510.0	17.0
	RT	117+52.00	122+62.00	510.0		153.0	510.0	17.0
	LT	123+70.00	124+70.00	200.0	(DOUBLE LINES)	60.0	200.0	6.7
		124+70.00	129+80.00	2040.0	(4 LINES)	612.0	2040.0	68.0
	CENTERLINE	129+80.00	147+85.00	3610.0	(DOUBLE LINES)	1083.0	3610.0	120.3
	LT	147+85.00	151+15.00	660.0	(DOUBLE LINES)	198.0	660.0	22.0
	CENTERLINE	152+15.00	153+45.00	260.0	(DOUBLE LINES)	78.0	260.0	8.7
		153+45.00	165+22.00	4708.0	(4 LINES)	1412.4	4708.0	156.9
	LT	165+22.00	166+00.00	156.0	(DOUBLE LINES)	46.8	156.0	5.2
	CENTERLINE	166+55.00	167+37.00	164.0	(DOUBLE LINES)	49.2	164.0	5.5
		167+37.00	174+09.00	2688.0	(4 LINES)	806.4	2688.0	89.6
	CENTERLINE	174+09.00	174+83.87 (BK)	149.7	(DOUBLE LINES)	44.9	149.7	5.0
		175+02.84 (AH)	180+30.00	527.2	NO PASSING	158.1	527.2	17.6
		363+85.00	376+71.30	1286.3	(DOUBLE LINES)	385.9	1286.3	42.9
		376+71.30	377+95.00	247.4	(DOUBLE LINES)	74.2	247.4	8.2
		377+95.00	381+35.00	1360.0	(4 LINES)	408.0	1360.0	45.3
		381+35.00	382+51.31	232.6	(DOUBLE LINES)	69.8	232.6	7.8
	LT	382+51.31	385+31.31	280.0		84.0	280.0	9.3
	RT	386+19.41	389+00.00	561.2		168.4	561.2	18.7
		389+00.00	394+79.41	2317.6	(4 LINES)	695.3	2317.6	77.3
		394+79.41	398+10.00	661.2	(DOUBLE LINES)	198.4	661.2	22.0
		496+84.00	502+49.00	565.0	NO PASSING	169.5	565.0	18.8
		502+49.00	507+09.00	1840.0	(4 LINES)	552.0	1840.0	61.3
		507+09.00	508+09.00	200.0	(2 LINES)	60.0	200.0	6.7
		508+93.00	509+93.00	200.0	(2 LINES)	60.0	200.0	6.7
		509+93.00	514+53.00	1840.0	(4 LINES)	552.0	1840.0	61.3
		514+53.00	520+22.00	569.0	NO PASSING	170.7	569.0	19.0
	US 136	614+26.00	618+66.00	1760.0	(4 LINES)	528.0	1760.0	58.7
	US 136 LT	618+66.00	619+66.00	200.0	(2 LINES)	60.0	200.0	6.7
	IL 11	620+50.00	621+50.00	200.0	(2 LINES)	60.0	200.0	6.7
	IL 11	621+50.00	626+00.00	1800.0	(4 LINES)	540.0	1800.0	60.0
	POLAND DR			88.0		17.6	88.0	2.0
	NEWELL RD			172.0		34.4	172.0	3.8
	SKIP-DASHES							
		62+23.58	68+90.00	333.2	(2 LINES)	-	333.2	-
		72+50.00	78+90.00	320.0	(2 LINES)	-	320.0	-
		79+94.00	93+54.00	680.0	(2 LINES)	-	680.0	-
		98+27.00	110+52.00	612.5	(2 LINES)	-	612.5	-
		111+56.00	112+06.00	25.0	(2 LINES)	-	25.0	-
		113+15.00	116+45.00	165.0	(2 LINES)	-	165.0	-
		117+52.00	122+62.00	127.5	(2 LINES)	-	127.5	-
	TOTAL =			44611.3		12678.4	44611.3	1408.7
	USE =			44612.0		12679.0	44612.0	1409.0

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -
ct:\pw\work\PWIDOT\BOWERML\0145216\70124 Schedules.dgn		DRAWN - MLB	REVISED -
		CHECKED -	REVISED -
		DATE - 08-20-2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

*(48-X)RS&(48-X2,RX,RX-1)RS-1				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	VERMILION	86	38
			CONTRACT NO. 70124	
ILLINOIS FED. AID PROJECT				