

78000200 THERMOPLASTIC PAVEMENT MARKING LINE-4" (WHITE)

70300100 SHORT TERM PVT MARKINGS

70300220 TEMP PVT MK LINE 4"

70301000 WORK ZONE PVT MK REM

78000400 THERMOPLASTIC PAVEMENT MARKING LINE-6" (WHITE)

STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	SQ FT
RT 69+22.00		70+20.00	98.0	29.4	98.0	98.0	3.3
LT 71+20.00		72+18.00	98.0	29.4	98.0	98.0	3.3
RT 94+04.00		95+67.00	163.0	48.9	163.0	163.0	5.4
RT 94+34.00		95+67.00	133.0	39.9	133.0	133.0	4.4
LT 96+79.00		97+85.00	106.0	31.8	106.0	106.0	3.5
LT 123+70.00		125+00.00	130.0	39.0	130.0	130.0	4.3
RT 133+28.00		150+87.00	1759.0	527.7	1759.0	1759.0	58.6
LT 137+63.00		150+91.00	1328.0	398.4	1328.0	1328.0	44.3
LT 150+15.00		151+15.00	100.0	30.0	100.0	100.0	3.3
RT 152+32.00		165+55.00	1323.0	396.9	1323.0	1323.0	44.1
LT 152+15.00		153+15.00	100.0	30.0	100.0	100.0	3.3
LT 152+57.00		174+83.87 (BK)	2226.9	668.1	2226.9	2226.9	74.2
LT 165+40.00		166+00.00	60.0	18.0	60.0	60.0	2.0
LT 166+55.00		167+15.00	60.0	18.0	60.0	60.0	2.0
RT 166+70.00		174+83.87 (BK)	813.9	244.2	813.9	813.9	27.1
LT 376+71.30		384+76.00	804.7	-	804.7	804.7	-
RT 376+71.30		384+76.00	804.7	-	804.7	804.7	-
RT 382+51.31		385+31.31	280.0	84.0	280.0	280.0	9.3
LT 386+19.41		389+00.00	280.6	84.2	280.6	280.6	9.4
LT 386+78.00		394+79.41	801.4	-	801.4	801.4	-
RT 386+78.00		394+79.41	801.4	-	801.4	801.4	-
RT 502+49.00		507+50.00	501.0	150.3	501.0	501.0	16.7
LT 502+49.00		507+50.00	501.0	150.3	501.0	501.0	16.7
RT 507+09.00		508+09.00	100.0	30.0	100.0	100.0	3.3
LT 508+93.00		509+93.00	100.0	30.0	100.0	100.0	3.3
RT 510+93.00		514+53.00	360.0	108.0	360.0	360.0	12.0
LT 510+93.00		514+53.00	360.0	108.0	360.0	360.0	12.0
RT 614+26.00		619+00.00	474.0 (US 136)	142.2	474.0	474.0	15.8
LT 614+26.00		619+00.00	474.0 (US 136)	142.2	474.0	474.0	15.8
RT 618+66.00		619+66.00	100.0 (US 136)	30.0	100.0	100.0	3.3
LT 620+50.00		621+50.00	100.0 (IL 119)	30.0	100.0	100.0	3.3
RT 621+25.00		626+00.00	475.0 (IL 119)	-	475.0	475.0	-
LT 621+25.00		626+00.00	475.0 (IL 119)	-	475.0	475.0	-
K's MERCHANDISE RD			39.0	7.8	39.0	39.0	0.9
SKIP-DASH							
LT 62+23.58		70+20.00	199.1	238.9	199.1	199.1	26.5
RT 62+23.58		70+20.00	199.1	238.9	199.1	199.1	26.5
LT 71+20.00		78+90.00	192.5	231.0	192.5	192.5	25.7
RT 71+20.00		78+90.00	192.5	231.0	192.5	192.5	25.7
LT 79+94.00		95+67.00	393.3	471.9	393.3	393.3	52.4
RT 79+94.00		95+67.00	393.3	471.9	393.3	393.3	52.4
LT 96+82.00		110+52.00	342.5	411.0	342.5	342.5	45.7
RT 96+82.00		110+52.00	342.5	411.0	342.5	342.5	45.7
LT 111+56.00		112+06.00	12.5	15.0	12.5	12.5	1.7
RT 111+56.00		112+06.00	12.5	15.0	12.5	12.5	1.7
LT 113+15.00		116+45.00	82.5	99.0	82.5	82.5	11.0
RT 113+15.00		116+45.00	82.5	99.0	82.5	82.5	11.0
LT 117+62.00		122+62.00	125.0	150.0	125.0	125.0	16.7
RT 117+62.00		122+62.00	125.0	150.0	125.0	125.0	16.7
LT 123+70.00		147+80.00	602.5	723.0	602.5	602.5	80.3
RT 123+70.00		151+15.00	688.3	823.5	688.3	688.3	91.5
RT 152+15.00		166+65.00	362.5	435.0	362.5	362.5	48.3
TOTAL =			20676.5	8861.8	20676.5	20676.5	984.6
USE =			20677.0	8862.0	20677.0	20677.0	985.0

LOCATION	FOOT	
POLAND RD.	159.0	(CROSSWALK)
REDBUD LANE	66.0	(CROSSWALK)
BOILING SPRINGS RD / K'S ENTRANCE	503.0	(CROSSWALK)
SONNY LANE	105.0	(CROSSWALK)
BISMARK RD	135.0	(ISLAND)
BISMARK RD	135.0	(ISLAND)
TOTAL =		1103.0
USE =		1103.0

78000600 THERMOPLASTIC PAVEMENT MARKING LINE-12" (WHITE)

LOCATION	FOOT	
BISMARK RD	120.0	(ISLAND)
BISMARK RD	120.0	(ISLAND)
TOTAL =		240.0
USE		240.0

78000600 THERMOPLASTIC PAVEMENT MARKING LINE-12" (YELLOW)

ALL YELLOW 12" LINES ARE DIAGONALS

STATION	TO	STATION	FOOT	
124+90.00		129+80.00	132.0	
153+45.00		155+45.00	36.0	
155+45.00		164+44.00	360.0	
164+44.00		165+22.00	18.0	
167+37.00		168+11.00	18.0	
168+11.00		174+09.00	600.0	
377+00.00		382+00.00	48.0	
389+00.00		394+00.00	48.0	
502+49.00		507+09.00	96.0	
507+09.00		508+09.00	6.0	
508+93.00		509+93.00	6.0	
509+93.00		514+53.00	96.0	
614+26.00		618+66.00	90.0	(US 136)
618+66.00		619+66.00	6.0	(US 136)
620+50.00		621+50.00	6.0	(IL 119)
621+50.00		626+00.00	90.0	(IL 119)
TOTAL =				1656.0
USE =				1656.0

FILE NAME =	USER NAME = bowerml	DESIGNED - MLB	REVISED -
ct:\pw\work\PWID01\BOWERML\0145216\70124 Schedules.dgn		DRAWN - MLB	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/27/2010	DATE - 08-20-2009	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.
--------	-----------	-----------	------	---------

*(48-X)IRS&(48-X2,RX,RX-1)RS-1				
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	*	VERMILION	86	39
			CONTRACT NO.	70124
ILLINOIS FED. AID PROJECT				