

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	CONSTRUCTION TYPE CODE:	LOCATION OF WORK:			
			MCLEAN CO.	MCLEAN CO.	MCLEAN CO.	MCLEAN CO.
			FAS 2484 IL 165	FAS 2484 IL 165	FAS 2484 IL 165	FAS 2484 IL 165
FUNDING BREAKOUT:		100% STATE	100% STATE	100% STATE	100% STATE	
UNIT	TOTAL	I000	X028-2A	SFTY-2A		
UNIT	QUANTITY	QUANTITY	QUANTITY	QUANTITY		
54020602	PRECAST CONCRETE BOX CULVERT 6' X 2' (M273)	FOOT	64.0		64.0	
54020603	PRECAST CONCRETE BOX CULVERT 6' X 3' (M273)	FOOT	38.0		38.0	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2.0	2.0		
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	43.5	43.5		
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	32.0	32.0		
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	3.0	3.0		
60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1.0	1.0		
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	1.0	1.0		
61100605	MISCELLANEOUS CONCRETE	CU YD	2.0	2.0		
61101013	STORM SEWERS PROTECTED, CLASS A, 12"	FOOT	120.0	120.0		
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	4.0	4.0		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	3,382.0	3,382.0		
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	12.0	12.0		
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	16.0	16.0		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	26.0	26.0		
63200310	GUARDRAIL REMOVAL	FOOT	3,800.0	3800.0		
63500105	DELINEATORS	EACH	8.0	8.0		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4.0	4.0		
67100100	MOBILIZATION	L SUM	1.0	1.0		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,829.0	7,829.0		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	101,090.0	101,090.0		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,292.0	1,292.0		
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	101,090.0	101,090.0		

* SPECIALTY ITEMS

FILE NAME =	USER NAME = coombessf	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\p\work\PM1001\C00MBESSF\dms87296\	70510-sht-500.dgn	DRAWN -	REVISED -			2484	125,126,127RS-2	MCLEAN	122	7	
	PLOT SCALE = 40,0000 ' / IN.	CHECKED -	REVISED -			CONTRACT NO. 70510					
	PLOT DATE = 1/22/2010	DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.