CONTRACT NO. 70529

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(102X)BR,BR-3	MCLEAN	42	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

LOCATION OF WORK:			ROADWAY	LOCATION 1	LOCATION 2
				S.N. 057-8302	S.N. 057-2039
CONSTRUCTION TYPE CODE:		80/20 FED/ST		STA. 40+618.180	44+045.000
		TOTAL	I000	X028-2A	X028-2A
CODE NO	ITEM	UNIT	QUANTITY		
M4400950	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ M	2,825.0	2,825.0	
M4402000	PAVEMENT REMOVAL	SQ M	424.0	424.0	
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	50.6	50.6	
M4402530	PAVED SHOULDER REMOVAL	SQ M	118.0	118.0	
M4405000	PAVED DITCH REMOVAL	METER	256.5	256.5	
M4428240	CLASS D PATCHES, TYPE II, 300MM	SQ M	108.0	108.0	
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	62.2	62.2	
M4820400	HOT-MIX ASPHALT SHOULDERS	M TON	164.4	164.4	
M4820550	HOT-MIX ASPHALT SHOULDERS, 150MM	SQ M	550.0	550.0	
M5401110	PRECAST CONCRETE BOX CULVERT 2.4M X 2.1M	METER	38.2		38.2
M5401190	PRECAST CONCRETE BOX CULVERT 3.3M X 2.4M	METER	44.2		44.2
M542E016	END SECTIONS 375MM	EACH	4.0	4.0	
M542E120	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 450MM	EACH	2.0	2.0	
M542E128	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 600MM	EACH	2.0	2.0	
M542H425	PIPE CULVERTS, CLASS D, TYPE 1 375MM	METER	20.1	20.1	
M542I030	PIPE CULVERTS, CLASS A, TYPE 2 450MM	METER	31.0	31.0	
M542I040	PIPE CULVERTS, CLASS A, TYPE 2 600MM	METER	30.9	30.9	
M6010120	PIPE DRAINS 250MM	METER	20.0	20.0	
M6110050	EXPLORATION TRENCH 1.3 METER DEPTH	METER	400.0	400.0	
M6110070	FIELD TILE JUNCTION VAULTS, 600MM DIA.	EACH	8.0	8.0	

CONT'D NEXT SHEET

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. ROUTE 315
SECTION (102X)BR,BR-3
MCLEAN COUNTY

DRAWN BY

DATE CHECKED BY

PLOT DATE = 1/28/2010
FILE NAME = c:\pw_wor\A\PWIDOT\SHERER,JM\d0106598\D578529-sht-esqu.dgn
PLOT SCALE = 27.0000 m / IN.
USER NAME = sherer_jm