

LOCATION OF WORK: FAU 6406 (US 150)
 MCLEAN COUNTY
 STA. 107+20.00 TO
 STA. 408+63.25
 URBAN

FUNDING BREAKOUT: 100% STATE

CONSTRUCTION TYPE CODE: 1000
 TOTAL

CODE NO	ITEM	UNIT	QUANTITY
20200500	EARTH EXCAVATION (WIDENING)	CU YD	114.0
31102100	SUB-BASE GRANULAR MATERIAL, TYPE C4"	SQ YD	340.0
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	12,048.0
40600300	AGGREGATE (PRIME COAT)	TON	242.0
40600895	CONSTRUCTING TEST STRIP	EACH	1.0
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4,654.0
40600990	TEMPORARY RAMP	SQ YD	207.0
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	4,551.0
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D" N50	TON	3,481.0
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	233.0
40800030	AGGREGATE (PRIME COAT)	TON	10.0
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	392.0
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	120,477.0
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	354.0
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	776.0
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	340.0
48203100	HOT-MIX ASPHALT SHOULDERS	TON	2,089.0
67100100	MOBILIZATION	L SUM	1.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,862.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	100,158.0
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	485.0
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,863.0
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	204.0

* SPECIALTY ITEMS

FILE NAME =	USER NAME = bowerml	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.U. RTE.	MCLEAN	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\PHIDOT\BOWERML\d0115116\d578339-shtr-sq.dgn		DRAWN -	REVISED -		6406	1RS-3	MCLEAN	33	4				
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 70539								
PLOT DATE = 1/29/2010		DATE -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		