

**PATCHING SCHEDULE**

(44200934)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II 8.0" (SQ. YD)	DOWEL BARS Z0017100 (EACH)	SAW CUTS 44213200 (FT)
131+87	EB	4	12	5.3	20	40.0
131+87	WB	4	12	5.3	20	40.0
144+47	EB	4	12	5.3	20	40.0
144+99	EB	4	12	5.3	20	40.0
144+99	WB	4	12	5.3	20	40.0
148+13	EB	4	12	5.3	20	40.0
148+13	WB	4	12	5.3	20	40.0
149+13	EB	4	12	5.3	20	40.0
149+13	WB	4	12	5.3	20	40.0
150+13	EB	4	12	5.3	20	40.0
150+13	WB	4	12	5.3	20	40.0
154+11	EB	4	12	5.3	20	40.0
154+11	WB	4	12	5.3	20	40.0
154+58	EB	4	12	5.3	20	40.0
154+58	WB	4	12	5.3	20	40.0
155+12	EB	4	12	5.3	20	40.0
155+12	WB	4	12	5.3	20	40.0
155+82	EB	4	12	5.3	20	40.0
155+82	WB	4	12	5.3	20	40.0
156+11	EB	4	12	5.3	20	40.0
156+11	WB	4	12	5.3	20	40.0
156+63	EB	4	12	5.3	20	40.0
156+63	WB	4	12	5.3	20	40.0
158+11	EB	4	12	5.3	20	40.0
158+11	WB	4	12	5.3	20	40.0
162+08	EB	4	12	5.3	20	40.0
162+08	WB	4	12	5.3	20	40.0
163+07	EB	4	12	5.3	20	40.0
163+07	WB	4	12	5.3	20	40.0
<b>SUB TOTALS</b>				154.7 (SQ. YD)	580.0 (EACH)	1160.0 (FT)

FILE NAME =	USER NAME = bucklesJJ	DESIGNED -	REVISED -
ct\pwork\work\PWIDOT\BUCKLESJJ\d0176654\0570817-Schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/15/2010	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
684	60PT	EDGAR	18	7
ILLINOIS FED. AID PROJECT			CONTRACT NO. 70817	