

**PATCHING SCHEDULE CONT.**

(44200934)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II 8.0" (SQ. YD)	DOWEL BARS Z0017100 (EACH)	SAW CUTS 44213200 (FT)
183+04	EB	4	12	5.3	20	40.0
183+04	WB	4	12	5.3	20	40.0
184+04	EB	4	12	5.3	20	40.0
184+04	WB	4	12	5.3	20	40.0
185+03	EB	4	12	5.3	20	40.0
185+03	WB	4	12	5.3	20	40.0
186+02	EB	4	12	5.3	20	40.0
186+02	WB	4	12	5.3	20	40.0
187+03	EB	4	12	5.3	20	40.0
187+03	WB	4	12	5.3	20	40.0
189+02	EB	4	12	5.3	20	40.0
189+02	WB	4	12	5.3	20	40.0
190+04	EB	4	12	5.3	20	40.0
190+04	WB	4	12	5.3	20	40.0
194+00	EB	4	12	5.3	20	40.0
194+00	WB	4	12	5.3	20	40.0
197+00	EB	4	12	5.3	20	40.0
197+00	WB	4	12	5.3	20	40.0
198+00	EB	4	12	5.3	20	40.0
198+00	WB	4	12	5.3	20	40.0
199+06	EB	6	12	8.0	20	42.0
199+06	WB	6	12	8.0	20	42.0
200+06	EB	4	12	5.3	20	40.0
200+06	WB	4	12	5.3	20	40.0
201+04	EB	4	12	5.3	20	40.0
201+04	WB	4	12	5.3	20	40.0
202+04	EB	6	12	8.0	20	42.0
202+04	WB	6	12	8.0	20	42.0
203+04	EB	8	12	10.7	20	44.0
203+04	WB	4	12	5.3	20	40.0
<b>SUB TOTALS</b>				176.0 (SQ. YD)	600.0 (EACH)	1212.0 (FT)

FILE NAME =	USER NAME = bucklesJJ	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pwwork\pwwid\BUCKLESJJ\d0176654\0570817-Schedule.dgn		DRAWN -	REVISED -					684	60PT	EDGAR	18	9
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:      SHEET NO.    OF    SHEETS    STA.            TO STA.			CONTRACT NO. 70817				
	PLOT DATE = 1/15/2010	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							