

**PATCHING SCHEDULE CONT.**

(44200934)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II 8.0" (SQ. YD)	DOWEL BARS Z0017100 (EACH)	SAW CUTS 44213200 (FT)
220+00	EB	4	12	5.3	20	40.0
220+00	WB	4	12	5.3	20	40.0
221+10	EB	4	12	5.3	20	40.0
221+10	WB	4	12	5.3	20	40.0
222+10	EB	4	12	5.3	20	40.0
222+10	WB	4	12	5.3	20	40.0
223+09	EB	4	12	5.3	20	40.0
223+09	WB	4	12	5.3	20	40.0
224+09	EB	4	12	5.3	20	40.0
224+09	WB	4	12	5.3	20	40.0
225+09	EB	4	12	5.3	20	40.0
225+09	WB	4	12	5.3	20	40.0
226+09	EB	4	12	5.3	20	40.0
226+09	WB	4	12	5.3	20	40.0
227+06	EB	4	12	5.3	20	40.0
227+06	WB	4	12	5.3	20	40.0
228+06	EB	4	12	5.3	20	40.0
228+06	WB	4	12	5.3	20	40.0
230+05	EB	4	12	5.3	20	40.0
230+05	WB	4	12	5.3	20	40.0
231+04	EB	4	12	5.3	20	40.0
231+04	WB	4	12	5.3	20	40.0
234+01	EB	4	12	5.3	20	40.0
234+01	WB	4	12	5.3	20	40.0
235+00	EB	4	12	5.3	20	40.0
235+00	WB	4	12	5.3	20	40.0
236+04	EB	4	12	5.3	20	40.0
236+04	WB	4	12	5.3	20	40.0
237+03	EB	4	12	5.3	20	40.0
237+03	WB	4	12	5.3	20	40.0
<b>SUB TOTALS</b>				160.0 (SQ. YD)	600.0 (EACH)	1200.0 (FT)

FILE NAME = c:\pwork\pwork\PWIDOT\BUCKLESJJ\d0176654\05	USER NAME = bucklesjj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	70817-Schedule.dgn	DRAWN -	REVISED -					684	60PT	EDGAR	18	11
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE:      SHEET NO.      OF      SHEETS      STA.      TO STA.			CONTRACT NO. 70817				
	PLOT DATE = 1/15/2010	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							