

PATCHING SCHEDULE CONT.

(44200934)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II 8.0" (SQ. YD)	DOWEL BARS Z0017100 (EACH)	SAW CUTS 44213200 (FT)
279+08	EB	4	12	5.3	20	40.0
279+08	WB	4	12	5.3	20	40.0
282+05	EB	6	12	8.0	20	42.0
282+05	WB	6	12	8.0	20	42.0
284+02	EB	4	12	5.3	20	40.0
284+02	WB	4	12	5.3	20	40.0
290+97	EB	4	12	5.3	20	40.0
290+97	WB	4	12	5.3	20	40.0
291+97	EB	4	12	5.3	20	40.0
291+97	WB	4	12	5.3	20	40.0
293+97	EB	4	12	5.3	20	40.0
293+97	WB	4	12	5.3	20	40.0
295+06	EB	4	12	5.3	20	40.0
295+06	WB	4	12	5.3	20	40.0
296+06	EB	4	12	5.3	20	40.0
296+06	WB	4	12	5.3	20	40.0
297+00	EB	4	12	5.3	20	40.0
297+00	WB	4	12	5.3	20	40.0
301+00	EB	4	12	5.3	20	40.0
301+00	WB	4	12	5.3	20	40.0
304+00	EB	4	12	5.3	20	40.0
304+00	WB	4	12	5.3	20	40.0
305+00	EB	4	12	5.3	20	40.0
305+00	WB	4	12	5.3	20	40.0
342+16	EB	4	12	5.3	20	40.0
342+16	WB	4	12	5.3	20	40.0
343+02	EB	4	12	5.3	20	40.0
343+02	WB	4	12	5.3	20	40.0
344+01	EB	4	12	5.3	20	40.0
344+01	WB	4	12	5.3	20	40.0
SUB TOTALS				165.3 (SQ. YD)	600.0 (EACH)	1204.0 (FT)

FILE NAME =	USER NAME = bucklesJJ	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct\pwwork\pwwid\BUCKLESJJ\d0176654\0570817-Schedule.dgn		DRAWN -	REVISED -					684	60PT	EDGAR	18	13
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 70817				
	PLOT DATE = 1/15/2010	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							