

PATCHING SCHEDULE CONT.

(44200934)

STATION	LANE	LENGTH (FT)	WIDTH (FT)	PATCH AREA TYPE II 8.0" (SQ. YD)	DOWEL BARS Z0017100 (EACH)	SAW CUTS 44213200 (FT)
346+02	EB	4	12	5.3	20	40.0
346+02	WB	4	12	5.3	20	40.0
347+02	EB	4	12	5.3	20	40.0
347+02	WB	4	12	5.3	20	40.0
348+02	EB	4	12	5.3	20	40.0
348+02	WB	4	12	5.3	20	40.0
350+00	WB	4	12	5.3	20	40.0
350+99	EB	4	12	5.3	20	40.0
350+99	WB	4	12	5.3	20	40.0
351+99	EB	4	12	5.3	20	40.0
351+99	WB	4	12	5.3	20	40.0
353+17	EB	4	12	5.3	20	40.0
353+17	WB	4	12	5.3	20	40.0
355+16	EB	4	12	5.3	20	40.0
355+16	WB	4	12	5.3	20	40.0
356+14	EB	4	12	5.3	20	40.0
356+14	WB	4	12	5.3	20	40.0
359+13	EB	6	12	8.0	20	42.0
359+13	WB	6	12	8.0	20	42.0
359+61	EB	6	12	8.0	20	42.0
359+61	WB	6	12	8.0	20	42.0
367+11	EB	10	12	13.3	20	46.0
367+11	WB	10	12	13.3	20	46.0
SUB TOTALS				149.3 (SQ. YD)	460.0 (EACH)	940.0 (FT)
TOTALS				1347.0 (SQ. YD)	4640.0 (EACH)	9362.0 (FT)

FILE NAME =	USER NAME = bucklesJJ	DESIGNED -	REVISED -
ct:\pw\work\PWIDOT\BUCKLESJJ\d0176654\0570817-Schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/15/2010	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
684	60PT	EDGAR	18	14
CONTRACT NO. 70817				
ILLINOIS FED. AID PROJECT				