

### SCHEDULE OF QUANTITIES

STATION	OFFSET DIR.	LENGTH	WIDTH	PATCH AREA				DOWEL BARS Z0017100 (each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PAVEMENT FABRIC 44213100 (sq. yd)
				TYPE I 12.0" (sq. yd)	TYPE II 12.0" (sq. yd)	TYPE III 12.0" (sq. yd)	TYPE IV 12.0" (sq. yd)				
106+87.50	RT	6	13	0	9	0	0	22	45	0	0
106+87.50	LT	6	13	0	9	0	0	22	45	0	0
107+07.50	RT	6	13	0	9	0	0	22	45	0	0
107+37.50	RT	6	13	0	9	0	0	22	45	0	0
107+37.50	LT	6	13	0	9	0	0	22	45	0	0
108+15.50	RT	6	13	0	9	0	0	22	45	0	0
108+88.50	RT	6	13	0	9	0	0	22	45	0	0
108+88.50	LT	6	13	0	9	0	0	22	45	0	0
109+88.50	RT	6	13	0	9	0	0	22	45	0	0
109+88.50	LT	6	13	0	9	0	0	22	45	0	0
111+72.50	RT	6	13	0	9	0	0	22	45	0	0
111+72.50	LT	6	13	0	9	0	0	22	45	0	0
113+91.50	RT	6	13	0	9	0	0	22	45	0	0
113+91.50	LT	6	13	0	9	0	0	22	45	0	0
114+49.50	RT	6	13	0	9	0	0	22	45	0	0
114+49.50	LT	6	13	0	9	0	0	22	45	0	0
111+04.17	RT	6	13	0	9	0	0	22	45	0	0
111+04.17	LT	15	13	0	0	22	0	22	54	0	22
115+11.17	RT	6	13	0	9	0	0	22	45	0	0
115+11.17	LT	6	13	0	9	0	0	22	45	0	0
117+08.17	LT	20	13	0	0	0	29	22	59	10	29
118+12.17	LT	6	13	0	9	0	0	22	45	0	0
118+12.17	RT	6	13	0	9	0	0	22	45	0	0
121+15.17	LT	12	13	0	0	17	0	22	51	0	17
122+12.17	LT	10	13	0	14	0	0	22	49	0	0
123+17.17	LT	20	13	0	0	0	29	22	59	10	29
124+16.17	LT	6	13	0	9	0	0	22	45	0	0
125+14.17	LT	8	13	0	12	0	0	22	47	0	0
125+14.17	RT	6	13	0	9	0	0	22	45	0	0
SUB TOTALS				0	225	39	58	638	1354	20	97
				(sq. yd)	(sq. yd)	(sq. yd)	(sq. yd)	(each)	(ft)	(each)	(sq. yd)