

SCHEDULE OF QUANTITIES

STATION	OFFSET DIR.	LENGTH (ft)	WIDTH (ft)	PATCH AREA				DOWEL BARS Z0017100 (each)	SAW CUTS 44213200 (ft)	TIE BARS Z0075300 (each)	PAVEMENT FABRIC 42001200 (sq. yd)				
				TYPE I 12.0" (sq. yd)	TYPE II 12.0" (sq. yd)	TYPE III 12.0" (sq. yd)	TYPE IV 12.0" (sq. yd)								
126+15.17	LT	6	13	0	9	0	0	22	45	0	0				
127+13.17	RT	8	13	0	12	0	0	22	47	0	0				
127+13.17	LT	6	13	0	9	0	0	22	45	0	0				
129+91.00	RT	6	13	0	9	0	0	22	45	0	0				
129+91.00	LT	6	13	0	9	0	0	22	45	0	0				
130+89.00	RT	6	13	0	9	0	0	22	45	0	0				
130+89.00	LT	10	13	0	14	0	0	22	49	0	0				
131+89.00	RT	6	13	0	9	0	0	22	45	0	0				
131+89.00	LT	6	13	0	9	0	0	22	45	0	0				
132+84.69	RT	6	13	0	9	0	0	22	45	0	0				
132+84.69	LT	6	13	0	9	0	0	22	45	0	0				
133+84.69	RT	12	13	0	0	17	0	22	51	0	17				
133+84.69	LT	12	13	0	0	17	0	22	51	0	17				
134+84.69	RT	10	13	0	14	0	0	22	49	0	0				
134+84.69	LT	12	13	0	0	17	0	22	51	0	17				
135+25.69	RT	12	13	0	0	17	0	22	51	0	17				
135+25.69	LT	12	13	0	0	17	0	22	51	0	17				
135+79.69	RT	20	13	0	0	0	29	22	59	10	29				
135+79.69	LT	20	13	0	0	0	29	22	59	10	29				
136+84.69	RT	12	13	0	0	17	0	22	51	0	17				
136+84.69	LT	12	13	0	0	17	0	22	51	0	17				
137+09.69	RT	6	13	0	9	0	0	22	45	0	0				
137+81.69	RT	30	13	0	0	0	43	33	69	15	43				
137+81.69	LT	6	13	0	9	0	0	22	45	0	0				
138+86.69	RT	12	13	0	0	17	0	22	51	0	17				
138+86.69	LT	12	13	0	0	17	0	22	51	0	17				
139+83.69	RT	12	13	0	0	17	0	22	51	0	17				
139+83.69	LT	12	13	0	0	17	0	22	51	0	17				
140+80.69	RT	12	13	0	0	17	0	22	51	0	17				
140+80.69	LT	12	13	0	0	17	0	22	51	0	17				
SUB TOTALS				0 (sq. yd)	136 (sq. yd)	225 (sq. yd)	101 (sq. yd)	671 (each)	1490 (ft)	35 (each)	326 (sq. yd)				
				PATCH AREA				DOWEL BARS		SAW CUTS		TIE BARS		PAVEMENT FABRIC	
				TYPE I 12.0" (sq. yd)	TYPE II 12.0" (sq. yd)	TYPE III 12.0" (sq. yd)	TYPE IV 12.0" (sq. yd)	Z0017100 (each)	44213200 (ft)	Z0075300 (each)	42001200 (sq. yd)				
TOTALS				0.0 (sq. yd)	361 (sq. yd)	264 (sq. yd)	159 (sq. yd)	1309 (each)	2844 (ft)	55 (each)	423 (sq. yd)				