

## SUMMARY OF QUANTITIES

90% FED. / 10% STATE

LOCATION OF WORK:

FAI - 55	FAI - 55
INTERSTATE	INTERSTATE
RURAL	URBAN
MCLEAN	MCLEAN
STA. 587+34.90	STA. 500+76.00
TO	TO
STA. 500+76.00	STA. 647+48.69

COUNTY:

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

1000-2A	1000-2A
---------	---------

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	63613.00	49532.00	14081.00
40600300	AGGREGATE (PRIME COAT)	TON	848.00	660.00	188.00
40600895	CONSTRUCTING TEST STRIP	EACH	1.00	0.80	0.20
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3854.00	3854.00	
40600990	TEMPORARY RAMP	SQ YD	1240.00	733.00	507.00
40603525	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N105	TON	42035.00	32730.00	9305.00
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	35623.00	27738.00	7885.00
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	420230.00	326356.00	93874.00
44200574	CLASS A PATCHES, TYPE I, 13 INCH	SQ YD	28.00	28.00	
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	175.00	127.00	48.00
44213000	PATCHING REINFORCEMENT	SQ YD	203.00	155.00	48.00
44213200	SAW CUTS	FOOT	1460.00	1100.00	360.00
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	7.00	5.00	2.00
67100100	MOBILIZATION	L SUM	1.00	0.80	0.20
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	14.00	8.00	6.00
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.00	0.80	0.20
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.00	0.80	0.20
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	50.00	40.00	10.00
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	44288.00	35116.00	9172.00
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	346867.00	278313.00	68554.00
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	8020.00	3710.00	4310.00
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	360.00		360.00
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	9437.00	7453.00	1984.00
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	306657.00	247313.00	59344.00
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	8020.00	3710.00	4310.00
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	360.00		360.00
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	40210.00	31000.00	9210.00
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4176.00	3157.00	1019.00
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4176.00	3157.00	1019.00
* X0301741	AERIAL SPEED CHECK MARKING	FOOT	96.00	96.00	
X0322729	MATERIAL TRANSFER DEVICE	TON	77658.00	60468.00	17190.00
X0323583	SPEED INDICATOR SIGN	CAL DA	170.00	85.00	85.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	42.00	14.00	28.00

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = piersonbr	DESIGNED - GAE	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
C:\pw_work\PIWIDOT\PIERSONBR\d0176190\05	0845-shr-500.dgn	DRAWN -	REVISED -		SCALE: NONE	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	55	5718.9,10RS-1	MCLEAN	23	5
	PLOT SCALE = 48.0000' / 1" IN.	CHECKED -	REVISED -										
	PLOT DATE = 2/4/2010	DATE - 12/09/09	REVISED -										
											CONTRACT NO. 70845		
											ILLINOIS FED. AID PROJECT		