

SUMMARY OF QUANTITIES

LOCATION OF WORK: F.A.I. - 74
 INTERSTATE
 RURAL
 COUNTY: MCLEAN
 FUNDING BREAK-OUT: 100% STATE
 FUNCTION TYPE CODE: I000-2A

ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40821.00
40600300	AGGREGATE (PRIME COAT)	TON	330.00
40600895	CONSTRUCTING TEST STRIP	EACH	2.00
40600990	TEMPORARY RAMP	SQ YD	58.00
40603245	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE COURSE, IL 19.0, N105	TON	19865.00
40603525	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N105	TON	3605.00
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	13835.00
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	57315.00
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	36784.00
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	36784.00
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	33790.00
67000500	ENGINEER FIELD OFFICE, TYPE B	CAL MO	6.00
67100100	MOBILIZATION	L SUM	1.00
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4.00
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.00
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.00
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	55.00
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16110.00
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	181170.00
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1500.00
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1770.00
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	161050.00
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1500.00
* 78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	20130.00
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	450.00
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	357.00
* X0301741	AERIAL SPEED CHECK MARKING	FOOT	24.00
X0322729	MATERIAL TRANSFER DEVICE	TON	36275.00
X0323583	SPEED INDICATOR SIGN	CAL DA	130.00
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.00

* SPECIALTY ITEM

FILE NAME *	USER NAME = ceerlockjd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\ph_work\PW100T\CEARLOCKJD\0182224\0570846-sht-500.dgn	DRAWN -	REVISED -	74			D5 INLAY 2010	MCLEAN	10	4		
PLOT SCALE = 48.0000 / IN.	CHECKED -	REVISED -	CONTRACT NO. 70846								
PLOT DATE = 2/4/2010	DATE - 01/29/10	REVISED -	ILLINOIS FED. AID PROJECT								
						SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.