

GENERAL NOTES

G.N.-100
ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-406
THE QUANTITIES INCLUDED IN THE PLANS FOR HOT-MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED TO INCREASE THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE IN ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.

G.N.-406.05b
ALL LEVELING BINDER, BINDER OR FIRST LIFT OF SURFACE COURSE SHALL BE GIVEN A FOG COAT OF PRIME BEFORE THE FINAL SURFACE COURSE IS PLACED WHEN DIRECTED BY THE ENGINEER.

THE FOG COAT WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER GALLON FOR BITUMINOUS MATERIAL (PRIME COAT) AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.

G.N.-406H
MIXTURE REQUIREMENTS

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

MIXTURE USES	AC/PG	RAP% (MAX)	DESIGN AIR VOIDS	MIXTURE COMPOSITION	FRICTION AGGREGATE
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "C", N105 (BOTTOM SURFACE LIFT)	SBS PG 70-22	10%	4.0% @ Ndes=105	IL 9.5	MIX "C"
POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE MIX "D", N105 (TOP SURFACE LIFT)	SBS PG 70-22	10%	4.0% @ Ndes=105	IL 9.5	MIX "D"

G.N.-442B - PATCHING SCHEDULES
THE PATCHING SCHEDULES INCLUDED IN THE PLANS REPRESENT THE BEST INFORMATION AVAILABLE AT THE TIME OF COMPLETION OF THE PLANS FOR LETTING. VARIATIONS IN LOCATION AND SIZES OF BOTH FULL-DEPTH AND PARTIAL-DEPTH PATCHES MAY OCCUR.

G.N.-703A
SHORT TERM PAVEMENT MARKING SHALL BE APPLIED TO THE PAVEMENT AFTER ANY OF THE FOLLOWING: COLD MILLING AND/OR PLACING BITUMINOUS MATERIALS (PRIME COAT), LEVELING BINDER (MACHINE METHOD), BINDER AND SURFACE COURSES. SHORT TERM PAVEMENT MARKING PLACED ON THE SURFACE, SHALL COINCIDE WITH THE FINAL PAVEMENT STRIPING. SHORT TERM PAVEMENT MARKING PLACED PRIOR TO THE SURFACE SHALL COINCIDE WITH THE EXISTING PAVEMENT MARKINGS. USE 4 FEET PER 40 FEET (OR 10% PER STATION).

G.N.-781A
DOUBLE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED ON ALL THE MULTI-LANE DIVIDED HIGHWAYS. THE LOCATION OF THE REFLECTIVE PAVEMENT MARKERS WILL BE IN ACCORDANCE WITH STANDARD 781001, AND THE DETAILS SHOWN IN THE PLANS. IF THERE IS ANY DISCREPANCY BETWEEN THE STANDARD AND THE DETAILS IN THE PLANS, THE DETAILS IN THE PLANS SHALL GOVERN. THE FINAL PAVEMENT MARKINGS SHALL BE IN PLACE PRIOR TO PLACING THE RAISED REFLECTIVE PAVEMENT MARKERS AND THE RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE PLACED MIDWAY IN THE 30 FOOT (9M) SPACE BETWEEN THE DASHED CENTERLINE STRIPES (WHEN APPLICABLE).

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS CONTRACT.

STRUCTURE INFORMATION

BASED ON STRUCTURAL ANALYSIS, THE FOLLOWING SHOULD BE NOTED WITH REGARDS TO MATERIAL TRANSFER DEVICES (MTD) TRAVELING OVER EXISTING STRUCTURES:

ONLY AN EMPTY MATERIAL TRANSFER DEVICE MAY PASS OVER THE FOLLOWING STRUCTURES:

057-0162	057-8301
057-0163	057-8510
057-0164	057-8511
057-0167	057-8512
057-0168	057-8513
057-0169	057-8514
057-0170	

FILE NAME :	USER NAME = piersonbr	DESIGNED - GAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw_work\FWIDOT\PIERSONBR\ad0176145\0570847-sht-gennote.dgn	DRAWN -	REVISED -	55			*	MCCLEAN	22	4	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -	*157-3-1,57-3,57-3-2,57-2\RS-1							
PLOT DATE = 2/4/2010	DATE - 12/30/09	REVISED -	SCALE: NONE			SHEET NO. 1	OF 1 SHEETS	STA. TO STA.	CONTRACT NO. 70847	ILLINOIS FED. AID PROJECT