

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI - 55

FAI - 55

FAI - 55

INTERSTATE

INTERSTATE

INTERSTATE

URBAN

RURAL

URBAN

COUNTY:

MCLEAN

MCLEAN

MCLEAN

STA. 114+64.00

STA. 279+78.00

STA. 198+00.00

TO

TO

ATR #5150 SITE

STA. 279+78.00

STA. 625+10.00

FUNDING BREAKOUT:

CONSTRUCTION TYPE CODE:

90/10 FED/ST

I000-2A

I000-2A

Y031-IF

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	QUANTITY	QUANTITY	QUANTITY
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	40190.00	15091.00	25099.00	
40600300	AGGREGATE (PRIME COAT)	TON	536.00	179.00	357.00	
40600895	CONSTRUCTING TEST STRIP	EACH	1.00	0.30	0.70	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	4160.00		4160.00	
40600990	TEMPORARY RAMP	SQ YD	1050.00	317.00	733.00	
40603525	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N105	TON	26557.00	9972.00	16585.00	
40603550	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105	TON	22506.00	7499.00	15007.00	
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	263772.00	89270.00	174502.00	
44200574	CLASS A PATCHES, TYPE I, 13 INCH	SQ YD	52.00	24.00	28.00	
44200610	CLASS A PATCHES, TYPE II, 13 INCH	SQ YD	112.00	54.00	58.00	
44213000	PATCHING REINFORCEMENT	SQ YD	164.00	78.00	86.00	
44213200	SAW CUTS	FOOT	1212.00	584.00	628.00	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	6.00	2.00	4.00	
67100100	MOBILIZATION	L SUM	1.00	0.30	0.70	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	9.00	2.00	7.00	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1.00	0.30	0.70	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1.00	0.30	0.70	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30.00	9.00	21.00	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	28176.00	9248.00	18928.00	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	227268.00	72866.00	154602.00	
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1800.00	1800.00		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6043.00	1982.00	4061.00	

* SPECIALTY ITEMS

FILE NAME =	USER NAME = piersonbr	DESIGNED - GAE	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C:\pwork\PIERSONBR\0176145\0570847-sht-500.dgn	0847-sht-500.dgn	DRAWN - BBP	REVISED -					55	*	MCLEAN	22	5
	PLOT SCALE = 40.0000 "/ IN.	CHECKED -	REVISED -		SCALE: NONE SHEET NO. 1 OF 2 SHEETS STA. TO STA.			*(57-3-1,57-3,57-3-2,57-2)RS-1		CONTRACT NO. 70847		
	PLOT DATE = 2/4/2010	DATE - 01/29/10	REVISED -		ILLINOIS FED. AID PROJECT							