

SCHEDULE OF QUANTITIES

CLASS A PATCHING SCHEDULE, 13"

LOCATION		STATION	LENGTH (FT)	WIDTH (FT)	44200574 TYPE I, 13" (SQ YD)	44200610 TYPE II, 13" (SQ YD)	44213200 SAW CUTS (FT)	44213000 PATCHING REINFORCEMENT (SQ YD)
N.B.	D.L.	120+00.00	6.00	12.00		8.00	60.00	8.00
N.B.	D.L.	144+00.00	6.00	12.00		8.00	60.00	8.00
N.B.	D.L.	146+00.00	6.00	6.00	4.00		36.00	4.00
N.B.	D.L.	150+00.00	6.00	12.00		8.00	60.00	8.00
N.B.	D.L.	250+00.00	6.00	12.00		8.00	60.00	8.00
N.B.	D.L.	322+00.00	6.00	12.00		8.00	60.00	8.00
N.B.	D.L.	445+00.00	6.00	6.00	4.00		36.00	4.00
N.B.	D.L.	447+00.00	6.00	6.00	4.00		36.00	4.00
N.B.	D.L.	500+00.00	10.00	12.00		13.33	68.00	13.33
N.B.	D.L.	560+00.00	6.00	6.00	4.00		36.00	4.00
N.B.	D.L.	570+00.00	6.00	6.00	4.00		36.00	4.00
N.B.	D.L.	571+00.00	6.00	6.00	4.00		36.00	4.00
N.B.	D.L.	615+00.00	6.00	12.00		8.00	60.00	8.00
S.B.	D.L.	115+00.00	6.00	12.00		8.00	60.00	8.00
S.B.	D.L.	118+00.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	140+00.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	142+00.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	144+00.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	240+60.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	239+36.00	10.00	12.00		13.33	68.00	13.33
S.B.	D.L.	322+30.00	6.00	12.00		8.00	60.00	8.00
S.B.	D.L.	321+69.00	10.00	12.00		13.33	68.00	13.33
S.B.	D.L.	464+00.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	609+00.00	6.00	6.00	4.00		36.00	4.00
S.B.	D.L.	618+00.00	6.00	12.00		8.00	60.00	8.00
TOTAL =					52.00	111.99	1212.00	163.99
USE =					52.00	112.00	1212.00	164.00
					(SQ YD)	(SQ YD)	(FT)	(SQ YD)

44000162 HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"

LOCATION		STATION	TO	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)
N.B.	D.L.	114+64.00		279+78.00	16514.00	12.00	22018.67
N.B.	P.L.	114+64.00		279+78.00	16514.00	12.00	22018.67
N.B.	D.L.	279+78.00		320+99.14	4121.14	12.00	5494.85
N.B.	P.L.	279+78.00		320+99.14	4121.14	12.00	5494.85
N.B.	D.L.	325+50.42		585+32.13	25981.71	12.00	34642.28
N.B.	P.L.	325+50.42		585+32.13	25981.71	12.00	34642.28
N.B.	D.L.	591+42.86		605+77.74	1434.88	12.00	1913.17
N.B.	P.L.	591+42.86		605+77.74	1434.88	12.00	1913.17
N.B.	D.L.	611+29.07		625+10.00	1380.93	12.00	1841.24
N.B.	P.L.	611+29.07		625+10.00	1380.93	12.00	1841.24
S.B.	D.L.	114+64.00		279+78.00	16514.00	12.00	22018.67
S.B.	P.L.	114+64.00		279+78.00	16514.00	12.00	22018.67
S.B.	A.L.	114+64.00		120+60.28	596.28	12.00	795.04
S.B.	A.L.	120+60.28		126+60.28	600.00	6.00	400.00
S.B.	D.L.	279+78.00		320+39.58	4061.58	12.00	5415.44
S.B.	P.L.	279+78.00		320+39.58	4061.58	12.00	5415.44
S.B.	D.L.	324+90.86		585+32.13	26041.27	12.00	34721.69
S.B.	P.L.	324+90.86		585+32.13	26041.27	12.00	34721.69
S.B.	D.L.	591+42.86		605+41.74	1398.88	12.00	1865.17
S.B.	P.L.	591+42.86		605+41.74	1398.88	12.00	1865.17
S.B.	D.L.	611+29.07		621+47.00	1017.93	12.00	1357.24
S.B.	P.L.	611+29.07		621+47.00	1017.93	12.00	1357.24
TOTAL =							263771.89
USE =							263772.00
							SQ YD
							SQ YD

NOTE:
 THE STATIONS LISTED FOR THE PATCHES ARE APPROXIMATE LOCATIONS.
 THE ACTUAL LOCATION AND SIZE SHALL BE FIELD VERIFIED AS SPECIFIED IN G.N.-442B.

LEGEND FOR SCHEDULE OF QUANTITIES			
N.B.	NORTHBOUND	D.L.	DRIVING LANE
S.B.	SOUTHBOUND	P.L.	PASSING LANE
C.L.	CENTERLINE	A.L.	AUXILIARY LANE