

SCHEDULE OF QUANTITIES

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
N.B. LT.	114+64.00		279+78.00	16514.00	YELLOW
N.B. RT.	114+64.00		243+20.00	12856.00	WHITE
N.B. RT.	247+50.00		268+10.00	2060.00	WHITE
N.B. RT.	272+80.00		279+78.00	698.00	WHITE
N.B. LT.	279+78.00		625+10.00	34532.00	YELLOW
N.B. RT.	279+78.00		625+10.00	34532.00	WHITE
N.B. C.L.	322+29.14		324+20.42	50.00	WHITE
N.B. C.L.	586+62.13		590+12.86	90.00	WHITE
N.B. C.L.	607+07.74		609+99.07	80.00	WHITE
S.B. RT.	114+64.00		279+78.00	16514.00	YELLOW
S.B. LT.	114+64.00		246+00.00	13136.00	WHITE
S.B. LT.	250+70.00		271+15.00	2045.00	WHITE
S.B. LT.	275+45.00		279+78.00	433.00	WHITE
S.B. RT.	279+78.00		621+47.00	34169.00	YELLOW
S.B. LT.	279+78.00		621+47.00	34169.00	WHITE
S.B. C.L.	321+69.58		323+60.86	50.00	WHITE
S.B. C.L.	586+62.13		590+12.86	90.00	WHITE
S.B. C.L.	606+71.74		609+99.07	80.00	WHITE
TOTAL =				202098.00	FT

NOTE:
 QUANTITIES SHOWN AT THE CENTERLINE (C.L.) ARE SKIP-DASH PAVEMENT MARKINGS FOR THE BRIDGE OMISSION LOCATIONS. THESE LOCATIONS ARE OMITTED FROM THE PREFORMED PLASTIC PAVEMENT MARKINGS TYPE B - LINE 4".

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

(I-55 GORE AREAS AT RAMPS)

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
N.B. RT.	243+20.00		247+50.00	430.00	WHITE
N.B. RT.	268+10.00		272+80.00	470.00	WHITE
S.B. LT.	246+00.00		250+70.00	470.00	WHITE
S.B. LT.	271+15.00		275+45.00	430.00	WHITE
TOTAL =				1800.00	FT

X0301741 AERIAL SPEED CHECK MARKING

STATION	LENGTH (FT)	COLOR
N.B. 167+90.00	12.00	WHITE
N.B. 174+50.00	12.00	WHITE
S.B. 441+50.00	12.00	WHITE
S.B. 448+10.00	12.00	WHITE
TOTAL =		48.00 FT

78003110 PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"

(I-55 CENTERLINE SKIP-DASH)

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
N.B. C.L.	114+64.00		279+78.00	4130.00	WHITE
N.B. C.L.	279+78.00		322+29.14	1060.00	WHITE
N.B. C.L.	324+20.42		586+62.13	6560.00	WHITE
N.B. C.L.	590+12.86		607+07.74	420.00	WHITE
N.B. C.L.	609+99.07		625+10.00	380.00	WHITE
S.B. A.L.	114+64.00		120+60.28	150.00	WHITE
S.B. C.L.	114+64.00		279+78.00	4130.00	WHITE
S.B. C.L.	279+78.00		321+69.58	1050.00	WHITE
S.B. C.L.	323+60.86		586+62.13	6580.00	WHITE
S.B. C.L.	590+12.86		606+71.74	420.00	WHITE
S.B. C.L.	609+99.07		621+47.00	290.00	WHITE
TOTAL =				25170.00	FT

70300220 TEMPORARY PAVEMENT MARKING - LINE 4"

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
N.B. LT.	114+64.00		279+78.00	16514.00	YELLOW
N.B. RT.	114+64.00		243+20.00	12856.00	WHITE
N.B. C.L.	114+64.00		279+78.00	4130.00	WHITE
N.B. RT.	247+50.00		268+10.00	2060.00	WHITE
N.B. RT.	272+80.00		279+78.00	698.00	WHITE
N.B. LT.	279+78.00		625+10.00	34532.00	YELLOW
N.B. RT.	279+78.00		625+10.00	34532.00	WHITE
N.B. C.L.	279+78.00		322+29.14	1060.00	WHITE
N.B. C.L.	322+29.14		324+20.42	50.00	WHITE
N.B. C.L.	324+20.42		586+62.13	6560.00	WHITE
N.B. C.L.	586+62.13		590+12.86	90.00	WHITE
N.B. C.L.	590+12.86		607+07.74	420.00	WHITE
N.B. C.L.	607+07.74		609+99.07	80.00	WHITE
N.B. C.L.	609+99.07		625+10.00	380.00	WHITE
S.B. RT.	114+64.00		279+78.00	16514.00	YELLOW
S.B. LT.	114+64.00		246+00.00	13136.00	WHITE
S.B. C.L.	114+64.00		279+78.00	4130.00	WHITE
S.B. A.L.	114+64.00		120+60.28	150.00	WHITE
S.B. LT.	250+70.00		271+15.00	2045.00	WHITE
S.B. LT.	275+45.00		279+78.00	433.00	WHITE
S.B. RT.	279+78.00		621+47.00	34169.00	YELLOW
S.B. LT.	279+78.00		621+47.00	34169.00	WHITE
S.B. C.L.	279+78.00		321+69.58	1050.00	WHITE
S.B. C.L.	321+69.58		323+60.86	50.00	WHITE
S.B. C.L.	323+60.86		586+62.13	6580.00	WHITE
S.B. C.L.	586+62.13		590+12.86	90.00	WHITE
S.B. C.L.	590+12.86		606+71.74	420.00	WHITE
S.B. C.L.	606+71.74		609+99.07	80.00	WHITE
S.B. C.L.	609+99.07		621+47.00	290.00	WHITE
TOTAL =				227268.00	FT

70300250 TEMPORARY PAVEMENT MARKING, LINE 8"

(I-55 GORE AREAS AT RAMPS)

LOCATION	STATION	TO	STATION	LENGTH (FT)	COLOR
N.B. RT.	243+20.00		247+50.00	430.00	WHITE
N.B. RT.	268+10.00		272+80.00	470.00	WHITE
S.B. LT.	246+00.00		250+70.00	470.00	WHITE
S.B. LT.	271+15.00		275+45.00	430.00	WHITE
TOTAL =				1800.00	FT

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

LOCATION	STATION	TO	STATION	LENGTH (FT)	QUANTITY (EACH)
N.B. C.L.	114+64.00		279+78.00	16514.00	414.00
N.B. RT.	243+20.00		247+50.00	430.00	12.00
N.B. C.L.	279+78.00		322+29.14	4251.14	106.00
N.B. C.L.	324+20.42		586+62.13	26241.71	656.00
N.B. C.L.	590+12.86		607+07.74	1694.88	42.00
N.B. C.L.	609+99.07		625+10.00	1510.93	38.00
S.B. A.L.	114+64.00		120+60.28	596.28	16.00
S.B. C.L.	114+64.00		279+78.00	16514.00	414.00
S.B. LT.	271+15.00		275+45.00	430.00	12.00
S.B. C.L.	279+78.00		321+69.58	4191.58	106.00
S.B. C.L.	323+60.86		586+62.13	26301.27	658.00
S.B. C.L.	590+12.86		606+71.74	1658.88	42.00
S.B. C.L.	609+99.07		621+47.00	1147.93	30.00
TOTAL =					2546.00 EACH

78100100 RAISED REFLECTIVE PAVEMENT MARKER

LOCATION	STATION	TO	STATION	LENGTH (FT)	QUANTITY (EACH)
N.B. C.L.	114+64.00		279+78.00	16514.00	414.00
N.B. RT.	243+20.00		247+50.00	430.00	12.00
N.B. C.L.	279+78.00		322+29.14	4251.14	106.00
N.B. C.L.	324+20.42		586+62.13	26241.71	656.00
N.B. C.L.	590+12.86		607+07.74	1694.88	42.00
N.B. C.L.	609+99.07		625+10.00	1510.93	38.00
S.B. A.L.	114+64.00		120+60.28	596.28	16.00
S.B. C.L.	114+64.00		279+78.00	16514.00	414.00
S.B. LT.	271+15.00		275+45.00	430.00	12.00
S.B. C.L.	279+78.00		321+69.58	4191.58	106.00
S.B. C.L.	323+60.86		586+62.13	26301.27	658.00
S.B. C.L.	590+12.86		606+71.74	1658.88	42.00
S.B. C.L.	609+99.07		621+47.00	1147.93	30.00
TOTAL =					2546.00 EACH

LEGEND FOR SCHEDULE OF QUANTITIES			
N.B.	NORTHBOUND	D.L.	DRIVING LANE
S.B.	SOUTHBOUND	P.L.	PASSING LANE
C.L.	CENTERLINE	A.L.	AUXILIARY LANE