

**SCHEDULE OF QUANTITIES
TABULATION OF CLASS A PATCH, 10"
I-39 MAINLINE (NORTHBOUND)**

STATION	LOCATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE I	TYPE II	TYPE III	SAWCUTS	PATCHING REINFORCEMENT *
					44200549 (SQ.YD.)	44200553 (SQ.YD.)	44200557 (SQ.YD.)	44213200 (FT)	44213000 (SQ.YD.)
239+50	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
240+55	I-39 MAINLINE	NBDL	6.0	12.0		8.0		60.0	8.0
255+00	I-39 MAINLINE	NBDL	6.0	12.0		8.0		60.0	8.0
255+40	I-39 MAINLINE	NBDL	6.0	12.0		8.0		60.0	8.0
256+90	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
257+00	I-39 MAINLINE	NBDL	15.0	6.0		10.0		54.0	10.0
260+20	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
264+20	I-39 MAINLINE	NBDL	18.0	12.0			24.0	84.0	24.0
273+40	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
278+50	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
284+50	I-39 MAINLINE	NBDL	6.0	12.0		8.0		60.0	8.0
287+00	I-39 MAINLINE	NBDL	6.0	12.0		8.0		60.0	8.0
299+50	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
303+00	I-39 MAINLINE	NBDL	15.0	6.0		10.0		54.0	10.0
303+15	I-39 MAINLINE	NBDL	15.0	6.0		10.0		54.0	10.0
358+00	I-39 MAINLINE	NBDL	6.0	6.0	4.0			36.0	4.0
370+50	I-39 MAINLINE	NBDL	6.0	12.0		8.0		60.0	8.0
PAGE SUBTOTALS OF CLASS A PATCH, 10 INCH					28.0	78.0	24.0	858.0	130.0

* LONGITUDINAL BARS ARE #7