

**SCHEDULE OF QUANTITIES  
TABULATION OF CLASS A PATCH, 10"  
I-39 MAINLINE (SOUTHBOUND)**

STATION	LOCATION	LANE	LENGTH (FT)	WIDTH (FT)	TYPE I	TYPE II	TYPE III	SAWCUTS (FT)	PATCHING REINFORCEMENT *
					44200549 (SQ.YD.)	44200553 (SQ.YD.)	44200557 (SQ.YD.)		44213000 (SQ.YD.)
507+50	I-39 MAINLINE	SBDL	6.0	12.0		8.0		66.0	8.0
507+20	I-39 MAINLINE	SBDL	6.0	12.0		8.0		66.0	8.0
472+70	I-39 MAINLINE	SBDL	12.0	12.0			16.0	84.0	16.0
472+20	I-39 MAINLINE	SBDL	6.0	6.0	4.0			42.0	4.0
399+30	I-39 MAINLINE	SBDL	10.0	12.0		13.3		78.0	13.3
377+00	I-39 MAINLINE	SBDL	8.0	12.0		10.7		64.0	10.7
363+00	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
362+80	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
362+60	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
309+00	I-39 MAINLINE	SBDL	10.0	12.0		13.3		68.0	13.3
298+40	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
297+00	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
296+40	I-39 MAINLINE	SBDL	10.0	6.0		6.7		44.0	6.7
254+00	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
252+50	I-39 MAINLINE	SBDL	15.0	6.0		10.0		54.0	10.0
238+50	I-39 MAINLINE	SBDL	6.0	6.0	4.0			36.0	4.0
237+80	I-39 MAINLINE	SBDL	6.0	12.0		8.0		60.0	8.0
475+00	I-39 MAINLINE	SBDL	6.0	12.0		8.0		66.0	8.0
476+00	I-39 MAINLINE	SBDL	6.0	12.0		8.0		66.0	8.0
477+00	I-39 MAINLINE	SBDL	6.0	12.0		8.0		66.0	8.0
478+00	I-39 MAINLINE	SBDL	6.0	12.0		8.0		66.0	8.0
<b>PAGE SUBTOTALS OF CLASS A PATCH, 10 INCH</b>					32.0	110.0	16.0	1142.0	158.0

\* LONGITUDINAL BARS ARE #7