| CONTRACT NO. 72533 |
FAP	SECTION	COUNTY	TOTAL SHEETS NO.	
310	69-12LS	MORGAN	16	2
STA.	TO STA.			
FED. ROJO DIST. MO.	ILLINOIS	FED. AID	PROJECT	

STATE

INDEX

- 1 COVER SHEET, STANDARD
- 2 INDEX, SUMMARY OF QUANITIES, GENERAL NOTES
- 3-16 LANDSCAPING PLANS

GENERAL NOTES

- THE TREES SHALL BE SPACED A MINIMUM OF 20 FEET APART.
- 2. THE LOCATIONS OF ALL PLANTS SHOWN ON THE PLANS ARE APPROXIMATE. THE DISTRICT LANDSCAPE ARCHITECT AND THE DEPARTMENT SHALL HAVE THE RIGHT TO ADJUST THE LOCATION OF PLANTS. NO ADDITIONAL COMPENSATION WILL BE ALLOWED THE CONTRACTOR FOR CONFORMING WITH THIS PROVISION.
- 3. CLASS 4 SEEDING AREAS SHALL EXTEND FROM A LINE 20 FEET FROM THE EDGES OF THE OUTSIDE SHOULDERS TO THE ACCESS CONTROL OR THE RIGHT-OF-WAY LINES AT THE LOCATIONS SHOWN ON THE PLANS.
- 4. THE SEEDING SHALL NOT BEGIN UNTIL ALL OTHER WORK HAS BEEN COMPLETED ON THIS SECTION UNLESS OTHERWISE DIRECTED BY THE LANDSCAPE ARCHITECT OR THE ENGINEER. NO FERTILIZER NUTRIENTS OR MULCH WILL BE REQUIRED FOR THE INTER SEEDING.
- 5. THE CONSTRUCTION LIMITS SHOWN ON THE PLANS
 ARE FOR THE GRADING AND PAVING OF THE VARIOUS
 CONSTRUCTION SECTIONS AND SHALL NOT BE CONSTRUED
 TO BE THE LIMITS FOR THE LANDSCAPING ON THIS PROJECT.

COMMITMENTS

AY CODE	ITEM	UNIT	TOTAL					QUANT	ITY PI	R SHEE	T					
ITEM				/3	4	5	6	7	8	9	10	11	12	13	14	15
5000750	MOWING	ACRE	38. 4	5. 4	4.8						3. 9	4. 8	5.5	2, 2	8. 1	1.9
5001800	SEEDING, CLASS 4 (MODIFIED)	ACRE	38. 4	5.4	4.8						3.9	4. 8	5.5	2. 2	8. 1	1.8
7100100	MOBILIZATION	L SUM	1												,	
2001020	TREE, ACER RUBRUM (RED MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	53	5	2	5	3		5	2	5	2	5	8	A	
2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	39	3	3	2	1/2	3	2		3	2	6	9/	5	
2002320	TREE, BETULA NIGRA (RIVER BIRCH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	20	5					2	4		5			2	2
2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALLED AND BURLAPPED	EACH	17	2	3					3		3		4		2
2007116	TREE, QUERCUS RUBBA (RED OAK), 2" CALIPER, BALLED AND BURLAPPED	EACH	24	2	3	2	2	0			3	/	5	2	2	
2007720	TREE, TAXODIUM DISTICHUM SHAWNEE BRAVE (SHAWNEE BRAVE BALD CYPRESS), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	8									3	2		3	
2001166	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	18			2					2		2		5	2
2001666	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 6' HEIGHT, SHRUB FORM, BALLED AND BURLAPPED	EACH	13	3		2			2			3				3
2001966	TREE, CRATAEGUS PHAENOPYRUM (WASHINGTON HAWTHORN), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	9		2			2			2					3
2003066	TREE, MALUS BRANDYWINE (BRANDYWINE CRAB APPLE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	10		3			3			2					2
2004316	TREE, MALUS RADIANT (RADIANT CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	20	3		3	F		3			2	3	R		
2005066	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	17	2		2/		2	3			2	2			2
2002972	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 6' HEIGHT, BALLED AND BURLAPPED	EACH	227		10		10	10	10		42	24	23	37	9	26
0026700	TREE CARE	EACH	2													
0026710	TREE CARE MULCH	L SUM	1													
0026720	TREE INTERMEDIATE AND SHRUB WATERING	UNIT.	5	/					 							

	SCALE: VERT.	DRAWN BY								
		AP ROUTE 310								
NAME	INDEX, SU	MMARY OF QUANTITIES, GENERAL NOTES								
REVISIONS NAME	DATE ILLINOIS DEF	ILLINOIS DEPARTMENT OF TRANSPORTATION								