

# SCHEDULE OF QUANTITIES

## HOT-MIX ASPHALT SURFACE REMOVAL

LOCATION	BUTT JT (SQ YD)	2" (SQ YD)	VAR DP (SQ YD)
F. A. P. 566 (IL 106)			
STA. 202+84.33 TO STA. 203+04.33	71.11		
STA. 205+48.00 TO STA. 216+98.40		4,090.31	
STA. 203+04.33 TO STA. 205+18.00			759.72
STA. 205+18.00 TO STA. 205+48.00			106.67
(STA. EQN. #1) - STA. 216+98.40 (BK) = 217+05.01 (AH)			
STA. 217+05.01 TO STA. 217+72.00		238.19	
STA. 217+72.00 TO STA. 217+82.00		32.22	
STA. 217+82.00 TO STA. 218+12.00			86.67
STA. 218+12.00 TO STA. 303+26.00			24,596.00
STA. 218+26.70 TO STA. 218+68.90 RT			32.82
STA. 304+26.00 TO STA. 304+78.00 RT			17.33
STA. 304+78.00 TO STA. 327+37.00			1,506.00
STA. 327+37.00 TO STA. 328+00.00 LT			21.00
STA. 333+94.00 TO STA. 353+25.00			1,287.33
STA. 377+35.00 TO STA. 378+00.00 LT			21.67
STA. 378+00.00 TO STA. 393+90.95			1,060.63
STA. 393+90.95 TO STA. 394+20.95	106.67		
LIMITS OF IMPROVEMENT - STA. 394+20.95			
BRIDGE OMISSION - S. N. 086-0501			
(STA. EQN. #2) - STA. 394+91.81 (BK) = 395+00.00 (AH)			
LIMITS OF IMPROVEMENT - STA. 395+70.86			
STA. 395+70.86 TO STA. 396+00.86	86.67		
STA. 400+20.00 TO STA. 401+43.00 RT			41.00
STA. 401+43.00 TO STA. 405+62.00 RT			279.33
STA. 405+62.00 TO STA. 408+23.00 LT			87.00
STA. 423+00.00 TO STA. 426+37.00 LT			112.33
STA. 426+37.00 TO STA. 432+80.00			428.67
STA. 437+80.84 TO STA. 438+10.84	86.67		
LIMITS OF IMPROVEMENT - STA. 438+10.84			
BRIDGE OMISSION - S. N. 086-0502			
(STA. EQN. #3) - STA. 438+84.64 (BK) = 438+80.00 (AH)			
LIMITS OF IMPROVEMENT - STA. 439+53.80			
STA. 439+53.80 TO STA. 439+83.80	106.67		
STA. 439+83.80 TO STA. 448+68.00			589.47
STA. 448+68.00 TO STA. 448+98.00	106.67		
INCIDENTAL BITUMINOUS SURFACING			
ENTRANCES			
	933.17		
SIDE ROADS			
	361.00		
PROJECT TOTAL			
	1,859	4,361	31,034

## TEMPORARY RAMP

LOCATION	QUANTITY (SQ YD)
F. A. P. 566 (IL 106)	
STA. 202+84.33 TO STA. 202+89.33	17.78
(STA. EQN. #1) - STA. 216+98.40 (BK) = 217+05.01 (AH)	
STA. 394+15.95 TO STA. 394+20.95	17.78
LIMITS OF IMPROVEMENT - STA. 394+20.95	
BRIDGE OMISSION - S. N. 086-0501	
(STA. EQN. #2) - STA. 394+91.81 (BK) = 395+00.00 (AH)	
LIMITS OF IMPROVEMENT - STA. 395+70.86	
STA. 395+70.86 TO STA. 395+75.86	14.44
STA. 438+05.84 TO STA. 438+10.84	14.44
LIMITS OF IMPROVEMENT - STA. 438+10.84	
BRIDGE OMISSION - S. N. 086-0502	
(STA. EQN. #3) - STA. 438+84.64 (BK) = 438+80.00 (AH)	
LIMITS OF IMPROVEMENT - STA. 439+53.80	
STA. 439+53.80 TO STA. 439+58.80	17.78
STA. 448+93.00 TO STA. 448+98.00	17.78
PROJECT TOTAL	
	100

## HOT-MIX ASPHALT SHOULDERS

LOCATION	QUANTITY (TON)
F. A. P. 566 (IL 106)	
STA. 202+84.33 TO STA. 216+98.40	118.78
(STA. EQN. #1) - STA. 216+98.40 (BK) = 217+05.01 (AH)	
STA. 217+05.01 TO STA. 217+72.00	5.63
STA. 217+72.00 TO STA. 217+82.00 RT	0.42
STA. 218+26.70 TO STA. 218+68.90 RT	4.14
PROJECT TOTAL	
	129

## INCIDENTAL HOT-MIX ASPHALT SURFACING

LOCATION	QUANTITY (TON)
PE'S AND CE'S	
	97.98
Side Roads	
	37.91
PROJECT TOTAL	
	136