

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

100% STATE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY 1000	STRUCTURES I-72 OVER CLEAR CREEK X031-2A	STRUCTURES I-72 OVER CLEAR CREEK TRIBUTARY X028-2A	STRUCTURES CH 34 OVER I-72 X231-2A
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	737	737			
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	75	75			
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	161	161			
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	182	182			
44200986	CLASS B PATCHES, TYPE III, 11 INCH	SQ YD	25	25			
<del>44213000</del>	<del>PATCHING REINFORCEMENT</del>	<del>SQ YD</del>	<del>3,391</del>	<del>3,391</del>			
44213100	PAVEMENT FABRIC	SQ YD	260	260			
44213200	SAW CUTS	FOOT	5,991	5,991			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	8,187	8,187			
<del>48102100</del>	<del>AGGREGATE WEDGE SHOULDER, TYPE B</del>	<del>TON</del>	<del>3,083</del>	<del>3,083</del>			
48203042	HOT-MIX ASPHALT SHOULDERS, 11 1/4"	SQ YD	1,200	1,200			
48203100	HOT-MIX ASPHALT SHOULDERS	TON	21,162	21,162			
48203049	HOT-MIX ASPHALT SHOULDERS, 13"	SQ YD	300	300			
50102400	CONCRETE REMOVAL	CU YD	32.2		24.2	8.0	
50200100	STRUCTURE EXCAVATION	CU YD	515			515	
50300225	CONCRETE STRUCTURES	CU YD	57.1		57.1		

Rev.

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
es:\pvc\work\FWIDOT\LAUGHLINRL\08184389\716SUM03.SHT	PLOT SCALE = NONE	DRAWN - AAD	REVISED -			72	084-10-2RS-3, 084-10-3RS-4	SANGAMON	61	5	
PLOT DATE = Feb-11-2010 08:45:05AM	DATE - 06/11/07	CHECKED - JAC	REVISED -			CONTRACT NO. 72910					
						SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT	