

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

100% STATE

DESCRIPTIONS				CONSTRUCTION TYPE CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000	STRUCTURES I-72 OVER CLEAR CREEK X031-2A	STRUCTURES I-72 OVER CLEAR CREEK TRIBUTARY X028-2A	STRUCTURES CH 34 OVER I-72 X231-2A
50300255	CONCRETE SUPERSTRUCTURE	CU YD	270.6		270.6		
50300260	BRIDGE DECK GROOVING	SQ YD	2,167.7		2,167.7		
50800105	REINFORCEMENT BARS	POUND	770	40		730	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	63,460		63,320	140	
50800515	BAR SPLICERS	EACH	492		492		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	180		180		
54003000	CONCRETE BOX CULVERTS	CU YD	16.7			16.7	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	9	9			
54215547	METAL END SECTIONS 12"	EACH	2	2			
54223459	REMOVE AND RELAY PIPE CULVERTS 24"	FOOT	64	64			
54223471	REMOVE AND RELAY PIPE CULVERTS 36"	FOOT	8	8			
54248510	CONCRETE COLLAR	CU YD	1	1			
54390180	INSERTION CULVERT LINER 24"	FOOT	118	118			
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	4		4		