

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

100% STATE

CODE NO.	DESCRIPTIONS ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE			
				ROADWAY 1000	STRUCTURES I-72 OVER CLEAR CREEK X031-2A	STRUCTURES I-72 OVER CLEAR CREEK TRIBUTARY X028-2A	STRUCTURES CH 34 OVER I-72 X231-2A
60100945	PIPE DRAINS 12"	FOOT	20	20			
60260100	INLETS TO BE ADJUSTED	EACH	5	5			
60260300	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1			
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	3,041	3,041			
60618760	CONCRETE MEDIAN, TYPE M-4.12	SQ FT	902	902			
60900240	TYPE C INLET BOX, STANDARD 609006	EACH	1	1			
60900315	TYPE D INLET BOX, STANDARD 609006	EACH	1	1			
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	550	550			
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
63200310	GUARDRAIL REMOVAL	FOOT	550	550			
63500105	DELINEATORS	EACH	312	312			
64200105	SHOULDER RUMBLE STRIP	FOOT	145,848	145,848			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	14	14			

\*Specialty Items Rev.

FILE NAME = c:\pv_work\PWIDOT\LAUHLINRL\j0184389\16SUM05.SHT	USER NAME = laughlinr1	DESIGNED -	REVISED -
PLOT SCALE = NONE	CHECKED - JAC	DATE - 06/11/07	REVISED -
PLOT DATE = Feb-11-2010 08:45:09AM			

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-10-2)RS-3, (84-10-3)RS-4	SANGAMON	61	7
CONTRACT NO. 72910				
FED. ROAD DIST. NO. 2 ILLINOIS FED. AID PROJECT				