

PAVEMENT MARKING SCHEDULE																	
LOCATION	LT / RT	PAINT PAVEMENT MARKING - LINE 5"			PREFORMED PLASTIC PAVEMENT MARKING, TY B - INLAID - LINE 6"	PREFORMED PLASTIC PAVEMENT MARKING, TY B - INLAID - LINE 12"	TEMPORARY PAINT PAVEMENT MARKING - LINE 5"			TEMP PAINT PAVEMENT MARKING - LINE 6"	TEMP PAINT PAVEMENT MARKING - LINE 12"	RAISED REFLECTIVE PAVEMENT MARKERS	SHORT-TERM PAVEMENT MARKING (2 APPLICATIONS)	WORK ZONE PAVEMENT MARKING REMOVAL			
		SOLID WHITE	SOLID YELLOW	SKIP DASHED YELLOW	SOLID WHITE	SOLID WHITE	SOLID WHITE	SOLID YELLOW	SKIP DASHED YELLOW	SOLID WHITE	SOLID WHITE						
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	SQ. FT.			
STA. 1698+55 TO STA. 1892+50	LT / RT	38,790								38,790				243	3,530	735	
STA. 1699+16 TO STA. 1700+00	CL			30								30					
STA. 1707+00 TO STA. 1729+00	CL			550								550					
STA. 1730+00 TO STA. 1752+00	CL			550	226					66		550	52	66			
STA. 1760+00 TO STA. 1774+00	CL			350								350					
STA. 1795+00 TO STA. 1890+09	CL			2,380								2,380					
NO PASSING ZONES																	
STA. 1698+55 TO STA. 1707+00	RT		845									845					
STA. 1700+00 TO STA. 1717+00	LT		1,700									1,700					
STA. 1719+00 TO STA. 1730+00	RT		1,100									1,100					
STA. 1729+00 TO STA. 1740+00	LT		1,100									1,100					
STA. 1749+00 TO STA. 1760+00	RT		1,100									1,100					
STA. 1752+00 TO STA. 1763+00	LT		1,100									1,100					
STA. 1763+00 TO STA. 1795+00	RT		3,200									3,200					
STA. 1774+00 TO STA. 1816+00	LT		4,200									4,200					
TOTALS		38,790	14,345	3,860	226	66	38,790	14,345	3,860	52	66	243	3,530	735			
		56,995			56,995												