

| SUMMARY OF QUANTITIES |  |       |       | STATE 100% |
|-----------------------|--|-------|-------|------------|
| PAY CODE              | ITEM DESCRIPTION                             | UNIT  | TOTAL | TOTAL      |
| 20200100              | EARTH EXCAVATION                             | CU YD | 29.0  | 29.0       |
| 20400800              | FURNISHED EXCAVATION                         | CU YD | 53.0  | 53.0       |
| 20800150              | TRENCH BACKFILL                              | CU YD | 40.0  | 40.0       |
| 21400100              | GRADING AND SHAPING DITCHES                  | FOOT  | 437.0 | 437.0      |
| 25000200              | SEEDING, CLASS 2                             | ACRE  | 0.4   | 0.4        |
| 25000400              | NITROGEN FERTILIZER NUTRIENT                 | POUND | 36.0  | 36.0       |
| 25000500              | PHOSPHORUS FERTILIZER NUTRIENT               | POUND | 36.0  | 36.0       |
| 25000600              | POTASSIUM FERTILIZER NUTRIENT                | POUND | 36.0  | 36.0       |
| 25000700              | AGRICULTURAL GROUND LIMESTONE                | TON   | 0.8   | 0.8        |
| 25100115              | MULCH, METHOD 2                              | ACRE  | 0.8   | 0.8        |
| 28000500              | INLET AND PIPE PROTECTION                    | EACH  | 14.0  | 14.0       |
| 31101000              | SUBBASE GRANULAR MATERIAL, TYPE B            | TON   | 8.0   | 8.0        |
| 35800100              | PREPARATION OF BASE                          | SQ YD | 625.0 | 625.0      |
| 35800200              | AGGREGATE BASE REPAIR                        | TON   | 14.0  | 14.0       |
| 40600200              | BITUMINOUS MATERIALS (PRIME COAT)            | TON   | 0.3   | 0.3        |
| 40600300              | AGGREGATE (PRIME COAT)                       | TON   | 1.0   | 1.0        |
| 40600982              | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 41.0  | 41.0       |
| 40800050              | INCIDENTAL HOT-MIX ASPHALT SURFACING         | TON   | 166.0 | 166.0      |
| 42400100              | PORTLAND CEMENT CONCRETE<br>SIDEWALK 4 INCH  | SQ FT | 516.0 | 516.0      |
| 42400800              | DETECTABLE WARNINGS                          | SQ FT | 78.0  | 78.0       |
| 44000100              | PAVEMENT REMOVAL                             | SQ YD | 60.0  | 60.0       |
| 44000500              | COMBINATION CURB AND GUTTER REMOVAL          | FOOT  | 68.0  | 68.0       |
| 44000600              | SIDEWALK REMOVAL                             | SQ FT | 414.0 | 414.0      |

| SUMMARY OF QUANTITIES |   |        |       | STATE 100% |
|-----------------------|---|--------|-------|------------|
| PAY CODE              | ITEM DESCRIPTION  | UNIT   | TOTAL | TOTAL      |
| 44200144              | PAVEMENT PATCHING, TYPE II, 12 INCH                     | SQ YD  | 17.0  | 17.0       |
| 50105220              | PIPE CULVERT REMOVAL                                    | FOOT   | 203.0 | 203.0      |
| 542A0220              | PIPE CULVERTS, CLASS A, TYPE 1 15"                      | FOOT   | 72.0  | 72.0       |
| 54213660              | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"     | EACH   | 5.0   | 5.0        |
| 54216555              | REINFORCED CONCRETE PIPE TEE, 15" PIPE WITH 15" RISER   | EACH   | 2.0   | 2.0        |
| 550A0070              | STORM SEWER CLASS A, TYPE 1 15"                         | FOOT   | 127.0 | 127.0      |
| 55100500              | STORM SEWER REMOVAL 12"                                 | FOOT   | 53.0  | 53.0       |
| 55100700              | STORM SEWER REMOVAL 15"                                 | FOOT   | 120.0 | 120.0      |
| 60218400              | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH   | 1.0   | 1.0        |
| 60218500              | MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE   | EACH   | 2.0   | 2.0        |
| 60236200              | INLETS, TYPE A, TYPE 8 GRATE                            | EACH   | 1.0   | 1.0        |
| 60240301              | INLETS, TYPE B, TYPE 8 GRATE                            | EACH   | 10.0  | 10.0       |
| 60500060              | REMOVING INLETS   | EACH   | 2.0   | 2.0        |
| 60605000              | COMBINATION CONCRETE CURB AND GUTTER, TYPE B6.24        | FOOT   | 66.0  | 66.0       |
| 67100100              | MOBILIZATION  | L SUM  | 1.0   | 1.0        |
| 70101830              | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21         | L SUM  | 1.0   | 1.0        |
| 70102620              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501         | L SUM  | 1.0   | 1.0        |
| 70102640              | TRAFFIC CONTROL AND PROTECTION, STANDARD 701801         | L SUM  | 1.0   | 1.0        |
| 70103815              | TRAFFIC CONTROL SURVEILLANCE                            | CAL DA | 20.0  | 20.0       |
| X0323382              | STORM SEWER, (WATER MAIN REQUIREMENT) TYPE 1, 15"       | FOOT   | 712.0 | 712.0      |
| XZ127900              | RETAINING WALL REMOVAL                                  | FOOT   | 143.0 | 143.0      |