

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS															
LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR HMA THICKNESS	HMA SURF. REM. - BUTT JOINT	P. C. C. SURF. REM. - BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE SURFACE COURSE TY - B	BIT (P. C.)	AGG (P. C.)	INCIDENTAL HMA SURF.
(LT / RT) (STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / BIT. / P. C. C.)	FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON
LT STA 451+65.00	PE/MB RURAL	AGG.	64		20	15	3.5			79		2	0.11	0.16	15
RT STA 454+82.00	PE RURAL	AGG.	16			15	3.5			44		2	0.06	0.09	9
LT STA 454+82.00	MB RURAL	AGG.	64			15	3.5			38		2	0.05	0.07	7
LT STA 491+18.00	PE/MB RURAL	BIT/AGG	64		20	15	3.5	70		70		2	0.10	0.14	14
LT STA 493+50.00	PE/MB RURAL	BIT/AGG	64		20	15	3.5	20		47		2	0.10	0.13	13
RT STA 507+50.00	PE RURAL	AGG.	20			15	3.5			50		2	0.07	0.10	10
LT STA 532+10.00	PE RURAL	AGG.	20			15	3.5			50		2	0.07	0.10	10
LT STA 568+83.00	PE RURAL	AGG.	20			15	3.5			50		2	0.07	0.10	10
RT STA 570+60.00	PE RURAL	AGG.	20			15	3.5			50		2	0.07	0.10	10
LT STA 572+20.00	PE/MB RURAL	BIT.	64	20		8	1.5	55					0.08	0.11	5
RT STA 574+10.00	PE RURAL	AGG.	20			15	3.5			47		2	0.07	0.10	9
LT STA 574+10.00	MB RURAL	AGG.	64			15	3.5			38		2	0.05	0.07	7
RT STA 583+60.00	PE RURAL	AGG.	20			15	3.5			50		2	0.07	0.10	10
LT STA 583+60.00	PE/MB RURAL	AGG.	64		20	15	3.5			70		2	0.10	0.14	14
LT STA 584+45.00	PE/MB RURAL	AGG.	64		20	15	3.5			70		2	0.10	0.14	14
LT STA 595+15.00	CE RURAL	BIT.	25			10	1.5	44					0.06	0.09	4
LT STA 616+60.00	CE RURAL	BIT.	35			10	1.5	56					0.08	0.11	5
LT STA 629+00.00	CE RURAL	AGG.	20			15	8.0			50		1	0.07	0.10	22
LT STA 632+50.00	CE URBAN	BIT.	40			10	1.5	61					0.09	0.12	5
LT STA 633+62.00	CE URBAN	BIT.	25			10	1.5	44					0.06	0.09	4
RT STA 633+70.00	CE URBAN	AGG.	30			4	8.0			13		2	0.02	0.03	6
RT STA 634+25.00	CE URBAN	BIT.	20			4	1.5	9					0.01	0.02	1
LT STA 635+60.00	CE URBAN	BIT.	20			4	1.5	9					0.01	0.02	1
RT STA 636+00.00	CE URBAN	BIT.	20			4	1.5	9					0.01	0.02	1
RT STA 636+45.00	CE URBAN	AGG.	18			4	8.0			8		1	0.01	0.02	4
LT STA 636+90.00	CE URBAN	BIT.	25			4	1.5	11					0.02	0.02	1
RT STA 637+05.00	CE URBAN	BIT.	15			4	1.5	7					0.01	0.01	1
RT STA 637+70.00	CE URBAN	BIT.	20			4	1.5	9					0.01	0.02	1
LT STA 638+00.00	PE URBAN	BIT.	15			4	1.5	7					0.01	0.01	1
LT STA 640+70.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
LT STA 641+60.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
LT STA 642+10.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
LT STA 642+50.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
RT STA 642+70.00	PE URBAN	BIT.	25			4	1.5	11					0.02	0.02	1
RT STA 645+65.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
LT STA 645+65.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
RT STA 646+12.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
RT STA 646+78.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
LT STA 649+25.00	PE URBAN	AGG.	20			4	3.5			9		2	0.01	0.02	2
RT STA 649+25.00	PE URBAN	BIT.	15			4	1.5	7					0.01	0.01	1
RT STA 650+30.00	PE URBAN	BIT.	15			4	1.5	7					0.01	0.01	1
LT STA 650+65.00	PE URBAN	BIT.	15			4	1.5	7					0.01	0.01	1
LT STA 652+00.00	PE URBAN	AGG.	40			4	3.5			18		3	0.03	0.04	3
RT STA 652+30.00	PE URBAN	AGG.	15			4	3.5			7		1	0.01	0.01	1
LT STA 652+50.00	CE URBAN	P. C. C.	18			4	1.5		8				0.01	0.02	1
TOTAL =								422	8	930		42	1.9	2.6	231

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED - 2/19/03 JCN
er\pwwork\PWIDOT\LAUGHLINRL\dms27159\672c28-sht-detail1.dgn		DRAWN - CADD	REVISED - 4/01/04 JCN
		CHECKED - JCN	REVISED -
		DATE - FEBRUARY 23, 1999	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**DIST. 6 DETAILS FOR RURAL/URBAN ENT., MAILBOX
TURNOUT & SIDEROADS W/O CONC. GUTTER (3P-PROJ.)**

SCALE: SHEET NO. 4 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
514	107RS-5	HANCOCK	30	22
CONTRACT NO. 72C28				
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				